

# EXPLOTECH

Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

## Blast Impact Analysis Uppers Quarry

Part of Lots 119, 120, 136 and 137, Part of the road allowance  
between Lots 120 and 136 (Geographic Township of Stamford), City  
of Niagara Falls, Regional Municipality of Niagara



Handwritten signature of A.M. Campbell.

Submitted to:

Walker Aggregates  
P.O. Box 100  
Thorold, Ontario  
Canada  
L2V 3Y8



Handwritten signature of R.J. Cyr.

Prepared by

Explotech Engineering Ltd.  
58 Antares Drive, Unit 5  
Ottawa, Ontario  
K2E 7W6

**Submitted – April 2024**



## EXECUTIVE SUMMARY

ExploTech Engineering Ltd. was retained in November 2016 to provide a Blast Impact Analysis for the proposed Uppers Quarry located on Part of Lots 119, 120, 136 and 137. The Assessment also takes into account potential extraction of the portion of Upper's Lane and part of the unopened road allowance between Lots 120 and 136 (geographic township of Stamford), where they exist between Thorold Townline Road and Beechwood Road, all in the City of Niagara Falls, Regional Municipality of Niagara.

Vibration levels assessed in this report are based on the Ministry of the Environment, Conservation and Parks (MECP) Model Municipal Noise Control By-law with regard to guidelines for blasting in Mines and Quarries. We have assessed the area surrounding the proposed licence area as it relates to potential damage from blasting operations and compliance with the aforementioned By-law document.

We have inspected the property and reviewed the available site plans. ExploTech is of the opinion that the planned aggregate extraction on the proposed property can be carried out safely and within MECP guidelines as set out in NPC 119 of the By-Law.



**TABLE OF CONTENTS**

**INTRODUCTION ..... 3**  
**EXISTING CONDITIONS ..... 5**  
**PROPOSED MINERAL EXTRACTION..... 9**  
**BLAST VIBRATION AND OVERPRESSURE LIMITS..... 11**  
**BLAST MECHANICS AND DERIVATIVES ..... 12**  
    VIBRATION AND OVERPRESSURE THEORY ..... 13  
    GROUND VIBRATION LEVELS AT THE NEAREST SENSITIVE RECEPTOR  
    ..... 14  
    OVERPRESSURE LEVELS AT THE NEAREST SENSITIVE RECEPTOR .... 19  
**ADDITIONAL CONSIDERATIONS OUTSIDE OF THE BLAST IMPACT**  
**ANALYSIS SCOPE ..... 23**  
    TC ENERGY HIGH PRESSURE NATURAL GAS PIPELINE ..... 23  
    FLYROCK..... 25  
        THEORETICAL HORIZONTAL FLYROCK CALCULATIONS ..... 25  
    TRANSMISSION AND HYDRO TOWERS ..... 29  
    RESIDENTIAL WATER WELLS ..... 30  
    BLAST IMPACT ON ADJACENT WATERCOURSES ..... 32  
**RECOMMENDATIONS ..... 34**  
**CONCLUSION ..... 36**

**APPENDIX A – OPERATIONAL PLAN**  
**SENSITIVE RECEPTOR OVERVIEWS**

**APPENDIX B – METEOROLOGICAL CONDITIONS**

**APPENDIX C – IMPERIAL AND METRIC VIBRATION AND OVERPRESSURE**  
**EQUATIONS AND ANALYSIS**

**APPENDIX D – CURRICULUM VITAE OF REPORT WRITERS**

**APPENDIX E – BLASTING TERMS & DEFINITIONS**  
**REFERENCES**



## **INTRODUCTION**

Walker Aggregates (Walker) intends to apply for a Class A, Category 2 Licence for the property legally described as Part of Lots 119, 120, 136 and 137, former Township of Stamford, now in the City of Niagara Falls, in the Regional Municipality of Niagara. Two municipal road allowances (Upper's Lane and an unopened road allowance between Part of Lots 120 and 136 in the former Township of Stamford) separate the proposed quarry site into three extraction areas:

- i) North Extraction Area: extraction area North of Upper's Lane;
- ii) Mid Extraction Area: extraction area South of Upper's Lane and North of the unopened road allowance between Township Lots 120 & 136 in the former Township of Stamford, now in the City of Niagara Falls ("unopened road allowance"); and
- iii) South Extraction Area: extraction area South of the unopened road allowance. Part of the road allowance between Lots 120 and 136 (geographic township of Stamford), City of Niagara Falls, Regional Municipality of Niagara.

This Blast Impact Analysis assesses the ability of the proposed licence (whether the two road allowances are ultimately included in the extraction area or not) to operate within the prescribed blast guideline limits as required by the Ontario Ministry of the Environment, Conservation and Parks (MECP).

While not specifically required as part of the scope of the Blast Impact Analysis under the Aggregate Resources Act, this report also touches on the topics of the flyrock and residential water wells for general informational purposes only. Details related to residential water wells are addressed in the hydrogeological report while specific flyrock control is addressed at the operational level given significant influences related to blast design, geology and field accuracy. Additionally, potential impacts on the adjacent TC Energy pipeline, electrical transmission towers, and nearby waterbodies are discussed to confirm compliance with applicable external corporate policies and guidelines.

The proposed Uppers Quarry operation is bounded by farm land to the North and South, Beechwood Road to the East, a residential subdivision (Fernwood) to the Southeast and Thorold Townline Road to the West. A residential and employment subdivision (Rolling Meadows) has been approved West of Thorold Townline Road. The extraction areas will be accessed via Thorold Townline Road and Upper's Lane.



The proponent currently owns the lands housing the residences designated as 5872 Thorold Townline Road and 5497 Beechwood Road. The closest sensitive receptor not owned by the proponent is the property designated as 5329 Beechwood Road.

This Blast Impact Analysis has been prepared based on the MECP Model Municipal Noise Control By-law with regard to Guidelines for Blasting in Mines and Quarries (NPC 119).

Given that mining operations have not been undertaken in the past on this property, site-specific blast monitoring data is not available. We have therefore applied data generated across a spectrum of quarries and construction projects which provides a conservative approximation of anticipated vibration levels from the operation. It has been our experience that this data represents a conservative starting point for blasting operations. It is a recommendation of this report that a vibration monitoring program be initiated on-site upon the commencement of blasting operations and maintained for the duration of all blasting activities to confirm compliance with MECP guideline limits for ground vibration and overpressure based on actual measurements taken during blast times.



## **EXISTING CONDITIONS**

The licenced area for the proposed Uppers Quarry encompasses a total area of approximately 103.6HA. The total extraction area is approximately 89.1HA.

The site is separated into eight (8) extraction phases. The phases are designated as 1a, 1b, 2a, 2b, 3a, 3b, 4 and 5 with phased extraction progressing initially from the Northwest corner of Phase 1a along the West end of the property (Refer to Appendix A).

The topography of the proposed licence area is generally lowest in the North portion of the site at an elevation in the order of 177masl rising towards the West and South with the highest elevations (185masl) lying in the middle of the West boundary of the site (Phase 1b). The design final quarry floor elevation is 141masl –148.7masl leading to the likely execution of 2 to 3 benches to achieve final grade.

The lands surrounding the proposed licence area are largely characterized by agricultural areas with a limited number of residential structures within 500m aside from a subdivision located Southeast of the boundary limits. All sensitive receptors within 500m of the licence boundary are as follows:

<b>Address</b>	<b>Distance to Receptor from Licence Boundary (m)</b>	<b>Direction from Licence Boundary</b>
9337 Beaversdam Road	475	North
9417 Beaversdam Road	447	North
9582 Beaversdam Road	151	North
9722 Beaversdam Road	234	North
10138 Beaversdam Road	442	North
10148 Beaversdam Road	184	North
5329 Beechwood Road	63	East
5584 Beechwood Road	81	Southeast
5769 Beechwood Road	287	Southeast
5821 Beechwood Road	360	Southeast
9312 Madison Crescent	417	Southeast
9315 Madison Crescent	445	Southeast
9324 Madison Crescent	404	Southeast
9325 Madison Crescent	434	Southeast

# EXPLOTECH

Address	Distance to Receptor from Licence Boundary (m)	Direction from Licence Boundary
9336 Madison Crescent	390	Southeast
9337 Madison Crescent	423	Southeast
9349 Madison Crescent	415	Southeast
9352 Madison Crescent	370	Southeast
9361 Madison Crescent	407	Southeast
9366 Madison Crescent	354	Southeast
9373 Madison Crescent	391	Southeast
9380 Madison Crescent	338	Southeast
9385 Madison Crescent	371	Southeast
9397 Madison Crescent	351	Southeast
9409 Madison Crescent	334	Southeast
9421 Madison Crescent	316	Southeast
9433 Madison Crescent	299	Southeast
9445 Madison Crescent	280	Southeast
9457 Madison Crescent	260	Southeast
5599 Osprey Avenue	251	Southeast
5607 Osprey Avenue	259	Southeast
5610 Osprey Avenue	311	Southeast
5615 Osprey Avenue	271	Southeast
5622 Osprey Avenue	323	Southeast
5623 Osprey Avenue	284	Southeast
5631 Osprey Avenue	290	Southeast
5632 Osprey Avenue	331	Southeast
5639 Osprey Avenue	299	Southeast
5642 Osprey Avenue	341	Southeast
5647 Osprey Avenue	311	Southeast
5652 Osprey Avenue	350	Southeast
5655 Osprey Avenue	321	Southeast
5663 Osprey Avenue	333	Southeast
5668 Osprey Avenue	362	Southeast
5671 Osprey Avenue	339	Southeast
5679 Osprey Avenue	350	Southeast
5687 Osprey Avenue	362	Southeast
5695 Osprey Avenue	374	Southeast

# EXPLOTECH

Address	Distance to Receptor from Licence Boundary (m)	Direction from Licence Boundary
5703 Osprey Avenue	383	Southeast
5711 Osprey Avenue	393	Southeast
5719 Osprey Avenue	404	Southeast
5727 Osprey Avenue	415	Southeast
5735 Osprey Avenue	424	Southeast
5743 Osprey Avenue	438	Southeast
5751 Osprey Avenue	448	Southeast
5759 Osprey Avenue	459	Southeast
5767 Osprey Avenue	470	Southeast
5772 Osprey Avenue	499	Southeast
5775 Osprey Avenue	480	Southeast
5783 Osprey Avenue	490	Southeast
9245 Shoveller Drive-Unit 1*	410	Southeast
9314 Shoveller Drive	494	Southeast
9324 Shoveller Drive	488	Southeast
9334 Shoveller Drive	478	Southeast
9344 Shoveller Drive	467	Southeast
9354 Shoveller Drive	460	Southeast
9364 Shoveller Drive	450	Southeast
9374 Shoveller Drive	443	Southeast
9384 Shoveller Drive	435	Southeast
9385 Shoveller Drive	392	Southeast
9394 Shoveller Drive	428	Southeast
9395 Shoveller Drive	383	Southeast
9404 Shoveller Drive	423	Southeast
9405 Shoveller Drive	374	Southeast
9414 Shoveller Drive	416	Southeast
9424 Shoveller Drive	412	Southeast
9434 Shoveller Drive	405	Southeast
9446 Shoveller Drive	400	Southeast
9045 Eagle Ridge Drive	457	Southeast
9355 Eagle Ridge Drive	494	Southeast
9365 Eagle Ridge Drive	481	Southeast
9375 Eagle Ridge Drive	469	Southeast

Address	Distance to Receptor from Licence Boundary (m)	Direction from Licence Boundary
9385 Eagle Ridge Drive	471	Southeast
9395 Eagle Ridge Drive	464	Southeast
9415 Eagle Ridge Drive	448	Southeast
9425 Eagle Ridge Drive	445	Southeast
9435 Eagle Ridge Drive	443	Southeast
9440 Eagle Ridge Drive-Unit 1*	484	Southeast
9445 Eagle Ridge Drive	436	Southeast
9461 Eagle Ridge Drive	427	Southeast
9484 Eagle Ridge Drive	480	Southeast
9490 Eagle Ridge Drive	478	Southeast
9494 Eagle Ridge Drive	477	Southeast
9500 Eagle Ridge Drive	474	Southeast

\*Multiple units located at address, closest unit to licence boundary included above

**Table 1: Sensitive Receptors within 500m of the Licence Boundary**

The properties on the proposed licenced land (5205 and 5497 Beechwood Road, 5872 Thorold Townline Road, 9764 Upper's Lane, 9903 Upper's Lane and 10200 Upper's Lane) are within the proposed extraction limits. Upon commencement of extraction, the use of these structures will be such that they do not qualify as sensitive receptors.

The utility buildings (4832 Thorold Townline Road) located directly adjacent the proposed licence do not qualify as sensitive receptors as defined by the MECP (refer to Appendix E for Definitions) but will remain in place and operational for the foreseeable future. In order to safeguard the integrity of this structure, we recommend that vibrations at the utility buildings be maintained below 50mm/s in accordance with research performed by the United States Bureau of Mines (USBM RI8507). It is a recommendation of this report that this structure shall be monitored for ground vibration when vibration calculations suggest vibrations in excess of 35mm/s.



## **PROPOSED MINERAL EXTRACTION**

An existing watercourse runs North-South through Phase 3a, Phase 4 and Phase 5 of the extraction limits. The proposed existing watercourse realignment will relocate the watercourse inside the excavation limits on the Western limits of extraction inside Phase 1b and 2b.

The extraction operations will begin with a sinking cut at the Northwest portion of Phase 1a (Mid Extraction Area) and will retreat Easterly and Southerly through Phase 1a. Phase 1b is located on the Western edge of Phase 1a and borders the Western most boundary for the proposed licence. In the Mid Extraction Area, Phase 1a will be extracted to a final floor elevation of 141 – 145masl and given existing topography of 181 – 185masl, it is anticipated that Phase 1a extraction will take place in 2 – 3 benches. Phase 1b will be extracted to a depth of no greater than 155masl in order to facilitate the construction of the new realigned watercourse. The Phase 1a and Phase 1b areas are also located in the South Extraction area separated by a road allowance not owned by the proponent. As a result, an additional sinking cut in the Northwest corner of Phase 1a (South Extraction Area) will be required. Phase 1a (South Extraction Area) will retreat Easterly and Southerly through Phase 1a (South Extraction Area). Phase 1b (South Extraction Area) is located on the Western edge of Phase 1a and borders the Western most boundary for the proposed licence. In the South Extraction Area, Phase 1a will be extracted to a final floor elevation of 141 – 145masl and given existing topography of 182 – 185masl, it is anticipated that Phase 1a (South Extraction Area) extraction will take place in 2 – 3 benches. Phase 1b (South Extraction Area) will be extracted to a depth of no greater than 155masl in order to facilitate the construction of the new realigned watercourse.

Phase 2a (North Extraction Area) is located North of Phase 1a and will begin with a sinking cut at the Southwest corner of Phase 2a and will retreat Easterly and Northerly through Phase 2a. Phase 2b is located on the Western and Northern edge of Phase 2a and borders the Western most boundary for the proposed licence. Phase 2a will be extracted to a final floor elevation of 144 – 145masl and given existing topography of 180 – 182masl, it is anticipated that Phase 2a extraction will take place in 2 – 3 benches. Phase 2b will be extracted to a depth no greater than an elevation of 155masl in order to facilitate the construction of the new realigned watercourse whereas the watercourse alignment transition area found at the North end of Phase 2b will only be extracted to a depth of no greater than 174masl in order to facilitate the construction of the new realigned watercourse.

Phase 3a (North Extraction Area) is located to the East of Phase 2a and is currently traversed by the existing watercourse. The existing watercourse is to be

# EXPLOTECH

relocated to the West perimeter of the site after the successful completion of the Phase 1b and 2b extraction.

A sinking cut in the Southwest corner of Phase 3b will initiate extraction with a Northerly and Easterly retreat. Extraction for Phase 3a will leverage the face created by extraction in Phase 2a with a Easterly retreat. \*\*\*

Phase 3a/3b will be extracted to a final floor elevation of 146masl – 149masl and given existing topography of 177masl – 183masl, it is anticipated that Phase 3 extraction will take place in 2 – 3 benches.

Phase 4 is located in the middle of the proposed licence area (Mid Extraction Area) and progresses from the Eastern Phase 1a limit (Mid Extraction Area) Easterly to the East proposed extraction limits. Extraction of Phase 4 will utilize the Eastern face of Phase 1a and will be extracted in 2 – 3 benches to a depth ranging from 141masl – 149masl given existing topography in Phase 4 of 177masl - 184masl.

Phase 5 is located in the South of the proposed licence area (South Extraction Area) and progresses from the Eastern Phase 1a limit (South Extraction Area) Easterly to the South and East extraction limits. Extraction of Phase 5 will utilize the Eastern face of Phase 1a and will be extracted in 2 – 3 benches to a depth ranging from 141masl – 149masl given existing topography in Phase 5 of 178masl - 182masl.

All extraction phases bordering the perimeter limits of the quarry (namely phases 1b, 2b, and 3a) will have a catchment bench located at elevation 149masl – 155masl depending on the phase.

As quarry operations migrate across the property, the closest sensitive receptors to the required blasting operations will vary. The closest receptor to the proposed Upper's Quarry licence area over the life of the quarry is 5329 Beechwood Road at a distance of 63m from the licence boundary.

---

\*\*\*Alternatively, if the existing watercourse is realigned prior to the extraction operations in Phase 3, extraction may begin in Phase 3a. Phase 3a will leverage the existing Phase 2a face and retreat Easterly. Phase 3b will then leverage the Phase 3a face and retreat Easterly. If this alternate extraction proceeds, the conclusions of this report are unchanged.



## **BLAST VIBRATION AND OVERPRESSURE LIMITS**

The Ontario MECP guidelines for blasting in quarries are among the most stringent in North America.

Studies by the U.S. Bureau of Mines have shown that normal temperature and humidity changes can cause more damage to residences than blast vibrations and overpressure in the range permitted by the MECP. The guideline limits set by the MECP are as follows.

**Vibration** \_\_\_\_\_ 12.5mm/sec      Peak Vector Sum (PVS)

**Overpressure** \_\_\_\_\_ 128 dBL      Peak Sound Pressure Level (PSPL)

The above guidelines apply when blasts are being monitored. Cautionary levels are slightly lower and apply when blasts are not monitored on a routine basis. It is a recommendation of this report that all blasts at the operation be monitored to quantify and record ground vibration and overpressure levels employing a minimum of two (2) digital seismographs, one installed at the closest sensitive receptor in front of the blast, or closer, and a second installed at the closest sensitive receptor behind the blast, or closer.



## **BLAST MECHANICS AND DERIVATIVES**

The detonation of explosives within a borehole results in the development of very high gas and shock pressures. This energy is transmitted to the surrounding rock mass, crushing the rock immediately surrounding the borehole (approximately 1 borehole radius) and permanently distorts the rock to several borehole diameters (5-25, depending on the rock type, prevalence of joint sets, etc.).

The intensity of this stress wave decays quickly so that there is no further permanent deformation of the rock mass. The remaining energy from the detonation travels through the unbroken material in the form of a pressure wave or shock front which, although it causes no plastic deformation of the rock mass, is transmitted in the form of vibrations.

Particle velocity is the descriptor of choice when dealing with vibrations because of its superior correlation with the appearance of cosmetic cracking. As such, for the purposes this report, ground vibration units have been listed in mm/s.

In addition to the ground vibrations; overpressure, or air vibrations are generated through the direct action of the explosive venting through cracks in the rock or through the indirect action of the rock movement. In either case, the result is a pressure wave which travels through the air, measured in decibels (or dB) for the purposes of this report.



## **VIBRATION AND OVERPRESSURE THEORY**

Transmission and decay of vibrations and overpressure can be estimated by the development of attenuation relations. These relations utilize empirical data relating measured velocities at specific separation distances from the vibration source to predict particle velocities at variable distances from the source. While the resultant prediction equations are reliable, divergence of data occurs as a result of a wide variety of variables, most notably site-specific geological conditions and blast geometry and design for ground vibrations and local prevailing climatic conditions for overpressure.

In order to circumvent this scatter and improve confidence in forecast vibration levels, probabilistic and statistical modeling is employed to increase conservatism built into prediction models, usually by the application of 95% confidence lines to attenuation data.

The attenuation relations are not designed to conclusively predict vibration levels at a specific location as a result of a specific blast design, application of this probabilistic model creates confidence that for any given scaled distance, 95% of the resultant velocities will fall below the calculated 95% regression line.

While the data still provides insight into probable vibration intensities, attenuation relations for overpressure tends to be less reliable and precise than results for ground vibrations. This is due primarily to wider variations in variables outside of the influence of the blast design which impact propagation of the vibrations. Atmospheric factors such as temperature gradients and prevailing winds (refer to Appendix B) as well as local topography can all serve to significantly alter overpressure attenuation characteristics. Fortunately, as described above, the conservatism built into the equations and the on-site vibration and overpressure monitoring performed at the quarry will aid in quantifying the vibrations and overpressures specific to the area in order to further reduce the likelihood of damage to all structures adjacent the quarry limits.

Our experience and analysis demonstrates that blast overpressure is greatest when blasting towards receptors, and blast vibrations are greatest when retreating towards the receptors.



## GROUND VIBRATION LEVELS AT THE NEAREST SENSITIVE RECEPTOR

The most commonly used formula for predicting Peak Particle Velocity (PPV) is known as the Bureau of Mines (BOM) prediction formula or Propagation Law. We have used this formula to predict the PPV's at the closest house for the initial operations.

$$PPV = k \left( \frac{d}{\sqrt{w}} \right)^e$$

Where, PPV = the predicted peak particle velocity (mm/s)

K, e = site factors

d = distance from receptor (m)

w = maximum explosive charge per delay (kg)

The value of K and e are variable and influenced by many factors (i.e. rock type, geology, thickness of overburden, etc.). As such, these site factors are developed empirically through the measurement of vibration characteristics at the specific operations of interested.

The portion of the BOM prediction formula contained within the parentheses is referred to as the *Scaled Distance* and represents another important PPV relation. It correlates the separation distance between a blast and receptor to the energy (usually expressed as explosive weight) released at any given instant in time. The two most popular approaches are square root scaling and cube root scaling:

$$\left( SDSR = \frac{R}{\sqrt{W}} \right)$$

$$\left( SDCR = \frac{R}{\sqrt[3]{W}} \right)$$

Where, SDSR = Scaled distance square root method

SDCR = Scaled distance cube root method

R = Separation distance between receptor site and blast (m)

W = Maximum explosive load per delay period (kg)

Historically, square root scaling is employed in situations whereby the explosive load is distributed in a long column (i.e. blasthole) while cube root scaling is employed for point charges. In accordance with industry standard, square root scaling was adopted for ground vibration analysis for the purposes of this report.

# EXPLOTECH

For a distance of 710m (the standoff distance to the closest sensitive receptor for the initial Phase 1a blasting (Mid Extraction Area), namely 10148 Beaversdam Road) and a maximum explosive load per delay of 118kg (101mm diameter hole, 15m deep, 3m surface collar and 1 hole per delay), we can calculate the maximum PPV at the closest building using the following formulae:

## Imperial Equations:

Oriard 50% Bound (2002)  $v = 160\left(\frac{D}{\sqrt{W}}\right)^{-1.6}$

Oriard 90% Bound (2002)  $v = 242\left(\frac{D}{\sqrt{W}}\right)^{-1.6}$

Quarry Production Blast  
(Bulletin 656 – 1971)  $v = 182\left(\frac{D}{\sqrt{W}}\right)^{-1.82}$

Typical limestone Quarry  
(Pader report – 1995)  $v = 52.2\left(\frac{D}{\sqrt{W}}\right)^{-1.38}$

Typical Coal Mine  
(RI8507 1980)  $v = 133\left(\frac{D}{\sqrt{W}}\right)^{-1.5}$

## Metric Equations:

General Blasting  
(Dupont)  $v = 1140\left(\frac{D}{\sqrt{W}}\right)^{-1.6}$

Construction Blasting  
(Dowding 1998)  $v = 1326\left(\frac{D}{\sqrt{W}}\right)^{-1.38}$

Agg. Quarry Blasting  
(Explotech 2005)  $v = 5175\left(\frac{D}{\sqrt{W}}\right)^{-1.76}$

Agg. Quarry blasting  
(Explotech 2003)  $v = 7025\left(\frac{D}{\sqrt{W}}\right)^{-1.85}$

# EXPLOTECH

The equations described above accommodate for a range of geological conditions. The proposed blast parameters were applied to the formulae to estimate a range of the potential vibrations to be imparted on the closest sensitive receptor behind the blast. As discussed in previous sections, the MECP guideline for blast-induced vibration is 12.5 mm/s (0.5 in/s). Appendix C demonstrates that the maximum (ie worst-case) calculated value for the vibration intensities imparted on the closest sensitive receptor based on all equations is 4.14mm/s for the initial blasting, well below the MECP guideline limit. All blasts will be monitored for overpressure and ground vibrations with blast designs adjusted in response to readings on site in order to confirm consistent compliance with established limits.

All vibration calculations and tables going forward will utilize the formula providing the worst case scenario for all geological conditions (Construction Blasting (Dowding 1998)).

An **example** of this calculation is as follows:

For a distance of 710m (the standoff distance to the closest sensitive receptor for the initial Phase 1a blasting, namely 10148 Beaversdam Road) and a maximum explosive load per delay of 118kg (101mm diameter hole, 15m deep, 3m surface collar and 1 hole per delay), we can calculate the maximum PPV at the closest sensitive receptor as follows:

$$ppv = 1326 \left( \frac{710}{\sqrt{118}} \right)^{-1.38} = 4.14 \text{ mm/s}$$

As discussed in previous sections, the MECP guideline for blast-induced vibration is 12.5 mm/s (0.5 in/s). The calculated 95% predicted PPV (based on the proposed blasting data discussed above) would be 4.14mm/s, well below the MECP guideline limit. It is understood that as separation distance to the receptors decreases, adjustments to blast designs may be necessary to maintain compliance with the guideline limits.

Similarly, the above equation used to calculate PPV can be reformatted to find an approximation of the distance at which a vibration velocity of 12.5mm/s would occur if all blasting parameters are kept the same as used in the equation above:

$$12.5 = 1326 \left( \frac{d}{\sqrt{118}} \right)^{-1.38} = 319.0 \text{ m}$$

# EXPLOTECH

The above result suggests that design modifications to the above preliminary design of an explosive load of 118kg/delay would be required once blasting operations encroach to within 319m of any sensitive receptor. Fortunately, vibration data will be continually collected and analyzed as the sensitive receptors are approached in order to confirm the requirement for any design modifications. An abundance of design modifications are available which would readily maintain vibration intensities below guideline limits. This is based on conservative assumptions which will be confirmed through monitoring.

Given the separation distances that will be involved at the proposed Uppers Quarry, Table 2 below provides initial guidance on maximum loads per delay based on various separation distances. The following maximum loads per delay were derived from the equation for ground vibrations listed above and are based on a maximum intensity of 12.5mm/s:

<b>Separation distance between sensitive receptor and closest borehole (meters)</b>	<b>Maximum recommended explosive load per delay (Kilograms)</b>
500	290
450	235
400	185
350	140
300	105
250	70
200	45
150	25
100	11

**Table 2: Maximum Loads per Delay to Maintain 12.5mm/s at Various Separation Distances**

It is noteworthy that the above values are typically conservative and are intended as a guideline only as the ground vibration attenuation equation is based on a calculated 95% regression line. Actual loads can be adjusted on the basis of the results of the monitoring program in place.

The closest separation distance between a sensitive receptor and the licence boundary is 63m. While blasting at this separation distance is feasible from a technological perspective, given current blasting technology and techniques, market economics will dictate the feasibility of extracting rock at lesser separation distances. Monitoring and changes in blasting designs will be required in order to



confirm all blasts are within MECP guidelines when blasting comes closer to adjacent sensitive receptors.

Similarly to the paragraph above, the closest separation distance between a non-sensitive receptor (namely the utility buildings located at 4832 Thorold Townline Road) and the extraction limits of the licence is 40m. Using the above equation and keeping the same blasting parameters with a suggested limit of 50mm/s, the calculation would suggest that once blasting encroaches to 116m removed from the utility buildings, modifications may be required.



## **OVERPRESSURE LEVELS AT THE NEAREST SENSITIVE RECEPTOR**

It is unusual for overpressure to reach damaging levels and when it does, the evidence is typically immediate and obvious in the form of broken windows in the area. However, overpressure remains of interest due to its ability to travel further distances as well as cause audible sounds and excitation in windows and walls.

Air overpressure decays in a known manner in a uniform atmosphere, however, a uniform atmosphere is not a normal condition. As such, air overpressure attenuation is far more variable due to its intimate relationship with environmental influences. Air vibrations decay slower than ground vibrations with an average decay rate of 6dB for every doubling of distance.

Air overpressure levels are analyzed using cube root scaling based on the following equation:

$$P = k \left( \frac{d}{\sqrt[3]{w}} \right)^e$$

Where, P = the peak overpressure level (psi – imperial, Pa, dB - metric)  
K, e = site factors  
d = distance from receptor (ft – imperial, m - metric)  
w = maximum explosive charge per delay (lbs – imperial, kg - metric)

The value of K and e are variable and are influenced by many factors (i.e. rock type, geology, thickness of overburden, environmental conditions, etc.). As such, these site factors are developed empirically through the measurement of overpressure characteristics at the specific operations of interested.

As discussed in previous sections, the MECP guideline for blast-induced overpressure is 128dB. For a distance of 710m (i.e. the standoff distance to the closest sensitive receptor in front of the blast for the initial Phase 1a blasting (Mid Extraction Area), namely 10148 Beaversdam Road) and a maximum explosive load of 118kg (101mm diameter hole, 15m deep, 3m surface collar and 1 hole per delay), we can calculate the overpressure at the nearest receptor in front of the blast using the following equations:

# EXPLOTECH

## Imperial Equations:

$$\text{USBM RI8485 (Behind Blast)} \quad P = 0.056 \left( \frac{D}{\sqrt[3]{W}} \right)^{-0.515}$$

$$\text{USBM RI8485 (Front of Blast)} \quad P = 1.317 \left( \frac{D}{\sqrt[3]{W}} \right)^{-0.966}$$

$$\text{USBM RI8485 (Full Confined)} \quad P = 0.061 \left( \frac{D}{\sqrt[3]{W}} \right)^{-0.96}$$

$$\text{Construction Average (Oriard 2005)} \quad P = 1 \left( \frac{D}{\sqrt[3]{W}} \right)^{-1.1}$$

## Metric Equations:

$$\text{Ontario Quarry - dB (Explotech)} \quad P = 159 \left( \frac{D}{\sqrt[3]{W}} \right)^{-0.0456}$$

$$\text{Limestone - dB (Explotech)} \quad P = 206 \left( \frac{D}{\sqrt[3]{W}} \right)^{-0.1}$$

$$\text{Ontario Quarry - Pa (Explotech)} \quad P = 1222 \left( \frac{D}{\sqrt[3]{W}} \right)^{-0.669}$$

Appendix C demonstrates that the maximum calculated value for the overpressure intensities imparted on the closest sensitive receptor based on all equations is 126.8 dB(L) for the initial blasting, below the MECP guideline limit. For initial blasting, all blasts should be scheduled on days with favourable weather conditions to assist in mitigating overpressure levels.

The initial blasting area is also located in the most optimal location such that the direction of extraction will only increase the distance removed from where the front face is directed towards the sensitive receptor. Every subsequent blast in Phase 1a when retreating to the East and South from the initial Phase 1a sinking cut area will result in progressively lower overpressure results. All blasts will be monitored for overpressure and ground vibrations with blast designs adjusted in response to readings on site in order to maintain consistent compliance with established limits.

# EXPLOTECH

Based on the above calculation and the assumed blast parameters, and the conservatism built into the equations, overpressures from blasting operations can remain compliant with the MECP NPC 119 guideline limit of 128dB(L). The design method of retreat has been planned so as to direct overpressures generated as much as practicable in the direction of vacant lands. All overpressure calculations and tables going forward will utilize the formula providing the worst case scenario for all geological conditions (Ontario Quarry – Pa (Explotech)).

We reiterate that air overpressure attenuation is far more variable due to its intimate relationship with environmental influences and as such, the equation employed is less reliable than that developed for ground vibration. Overpressure monitoring performed on site shall be used to guide blast design as it pertains to the control of blast overpressures. As demonstrated in Appendix B, prevailing winds during quarry operational periods are predominantly out of the Southwest.

The overpressure equation used to calculate PSPL can be reformatted to find an approximation of the distance at which an overpressure of 128 dB(L) would occur. If all blasting parameters are kept the same as above, a distance of 580m from the closest sensitive receptor in front of the blast would have a calculated overpressure of 128db(L). Once again, the on-site monitoring program will accurately delineate the overpressure intensities and provide guidance for the timing for any design changes.

Given the correlation between overpressure and environmental conditions as stated previously, care must be taken to avoid blasting on days when weather patterns are less favourable. Extraction directions have been selected so as to minimize overpressure impacts on adjacent receptors.

Table 3 below can be used as an initial guide showing maximum loads per delay based on various separation distances for receptors in front of the blast face. The following maximum loads per delay are derived from the air overpressure equation above and are based on a peak overpressure level of 128dB(L):



Separation distance between sensitive receptor and closest blasthole (meters)	Maximum recommended explosive load per delay (Kilograms)
1000	610
900	440
800	310
700	208
600	130
500	75

**Table 3: Maximum Calculated Loads per Delay to Maintain 128dB(L) at Various Separation Distances for Receptors in Front of the Face**

We note that the above values are conservative and are intended as a guideline only as the air overpressure attenuation is based on a calculated 95% regression line. Actual loads employed shall be based on the results of the monitoring program in place.



## ADDITIONAL CONSIDERATIONS OUTSIDE OF THE BLAST IMPACT ANALYSIS SCOPE

The following headings are addressed for general information purposes and are not strictly required as part of the scope of the Blast Impact Analysis as required under the ARA to assess compliance with MECP NPC-119 guidelines. Considerations for the TC Energy Pipeline and Hydro One transmission towers can be expanded upon under separate cover with direct input from the owners as required. The hydrogeological study prepared by WSP as part of the licence application will address residential water wells in detail. Flyrock control is addressed at the operational level given significant influences related to blast design, geology and field accuracy which render concrete recommendations related to control inappropriate at the licencing phase. Considerations for aquatic species in the existing watercourse are further addressed in the Stantec report.

### TC ENERGY HIGH PRESSURE NATURAL GAS PIPELINE

A TC Energy High Pressure Natural Gas Pipeline runs adjacent to the Northwest corner of the proposed quarry limits (refer to Appendix A). The MECP guideline for blast-induced vibration (12.5mm/s) does not apply to pipelines as they are not classified as sensitive receptors. Two (2) welded steel pipelines exist within the TC Energy right of way (ROW), one 20" and one 36" diameter pipeline. TC Energy Policy employs a 50mm/s vibration limit for welded steel pipelines. Based on the proposed Operations Plan for the Uppers Quarry, initial blasting operations are anticipated to be required approximately 345m from the subject pipeline, however, will reach as close as 7m throughout the course of extraction.

Applying the equation from Predicated Vibration Limits at the Nearest Sensitive Receptor, for a distance of 345m (the conservative standoff distance to the pipeline for the initial blasting (Mid Extraction Area)) and a maximum explosives load per delay of 118kg (101mm diameter hole, 15m deep, 3m surface collar and 1 hole per delay), we can calculate the maximum PPV at the pipeline as follows for the initial blast:

$$ppv = 1326 \left( \frac{345}{\sqrt{118}} \right)^{-1.38} = 11.22 \text{ mm/s}$$

The calculated 95% predicted PPV (based on the proposed blasting data discussed above) would be 11.22mm/s, well below the TC Energy limit of 50mm/s for a steel welded pipeline located adjacent to the proposed quarry.

# EXPLOTECH

While this initial value resides below the required threshold, it is anticipated that design modifications will be necessary to maintain compliance as the separation distance to the pipeline decreases and column loads increase. Fortunately, a variety of blast design alternatives are available to accomplish this including but not limited to reductions in blast hole diameter, change in explosives types, adjustment in bench heights and decking of holes.

We do note that the TC Energy Blasting Specification requires the presence of a vibration monitoring program when blasting operations are to be conducted within 100m of a pipeline. The proposed Operational Plan dictates that blasting is to encroach within 7m of the ROW and as such, it is a recommendation of this report that an independent third party firm be retained to conduct vibration monitoring on this pipeline when separation encroaches within 100m of the pipeline or when calculations suggest ground vibrations in excess of 35mm/s as measured at the pipeline are anticipated. The results of this monitoring program will determine what blast design alterations shall be necessary as the separation distance to the subject pipeline decreases. Walker will adhere to the guidelines set by TC Energy with respect to blasting in proximity of the gas lines.

# EXPLOTECH

## FLYROCK

Flyrock is the term used to define rocks which are propelled from the blast area by the force of the explosion. This action is a predictable and necessary component of a blast and requires that every blast have an exclusion zone established within which no persons or property which may be harmed are permitted.

Government regulations strictly prohibit the ejection of flyrock off of a quarry property. The regulations regarding flyrock are enforced by the Ministries of Natural Resources, Environment and Labour. In the event of an incident where flyrock does leave a site, the punitive measures include suspension / revocation of licences and fines to both the blaster and quarry owner / operator. Fortunately, flyrock incidents are extremely rare due to the possible serious consequences of such an event. It is in the best interest of all, stakeholders and non-stakeholders, to ensure that dangerous flyrock does not occur. Through proper blast planning and design, it is possible to control and mitigate the possibility for flyrock.

## THEORETICAL HORIZONTAL FLYROCK CALCULATIONS

Flyrock occurs when explosives in a hole are poorly confined by the stemming or rock mass and the high pressure gas breaks out of confinement and launches rock fragments into the air. The three primary sources of fly rock are as follows:

- **Face burst:** Lack of confinement by the rock mass in front of the blast hole results in fly rock in front of the face.
- **Cratering:** Insufficient stemming height or weakened collar rock results in a crater being formed around the hole collar with rock projected in any direction.
- **Stemming Ejection:** Poor stemming practice can result in a high angle throw of the stemming material and loose rocks in the blasthole wall and collar.

The horizontal distance flyrock can be thrown ( $L_H$ ) from a blast hole is determined using the expression:

$$L_H = \frac{V_o^2 \sin 2\theta_0}{g} \quad [1]$$

# EXPLOTECH

where:  $V_o$  = launch velocity (m/s)  
 $\theta_0$  = launch angle (degrees)  
 $g$  = gravitational constant (9.8 m/s<sup>2</sup>)

The theoretical maximum horizontal distance fly rock will travel occurs when  $\theta_0 = 45$  degrees, thereby yielding the equation:

$$L_{H \max} = \frac{V_o^2}{g} \quad [2]$$

The normal range of launch velocity for blasting is between 10m/s - 30m/s. To calculate the launch velocity of a blast the following formula is used:

$$V_o = k \left( \frac{\sqrt{m}}{B} \right)^{1.3} \quad [3]$$

where:  $k$  = a constant  
 $m$  = charge mass per meter (kg/m)  
 $B$  = burden (m)

By combining equations 2 and 3 and taking into account the different sources of fly rock, the following equations can be used to calculate the maximum fly rock thrown from a blast:

Face burst: 
$$L_{H \max} = \frac{k^2}{g} * \left( \frac{\sqrt{m}}{B} \right)^{2.6}$$

Cratering: 
$$L_{H \max} = \frac{k^2}{g} * \left( \frac{\sqrt{m}}{SH} \right)^{2.6}$$

# EXPLOTECH

Stemming Ejection: 
$$L_{H \max} = \frac{k^2}{g} * \left( \frac{\sqrt{m}}{SH} \right)^{2.6} \sin 2\theta$$

- where:
- $\theta$  = drill hole angle
  - $L_{H \max}$  = maximum flyrock throw (m)
  - $m$  = charge mass per meter (kg/m)
  - $B$  = burden (m)
  - $SH$  = stemming height (m)
  - $g$  = gravitational constant
  - $k$  = a constant

The range for the constant  $k$  is 13.5 for soft rocks and 27 for hard rocks. Given the proposed licence area is predominantly limestone, we have applied a  $k$  value of 21. The explosive density is assigned to be 1.2 g/cc for emulsion products and the drill hole angles are assumed to be 90 degrees (i.e. vertical).

For calculation purposes, we have applied the initial blasting parameters which utilize 101mm (4") diameter holes on a 3.05m x 3.05m (10' x 10') pattern, with a lift height of 15m (49') and a collar length of 3.0m (10'). The following does not apply to the sinking cut which will require highly specialized designs and additional considerations for flyrock. Based on a free face blast, maximum anticipated horizontal flyrock projection distances are calculated as follows in Table 4:

<b>Table 4 – Maximum Flyrock Horizontal</b>		
<b>Collar Lengths</b> (m)	<b>Maximum Throw Face Burst</b> (m)	<b>Maximum Throw Cratering and Stemming Ejection</b> (m)
1.5	48	302
2.0	48	143
2.5	48	80
3.0	48	50
3.5	48	33

# EXPLOTECH

Different collar lengths are displayed in the table above to account for over or under loaded holes. As demonstrated with these various collar lengths, any deviation, no matter how slight, can greatly affect these maximum values. The current proposed initial blasting parameters have the potential to send flyrock 50m assuming all holes achieve the designed collar lengths of 3.0m. Blast mats or sand can be placed on top of the initial blast to further reduce the distance for potential flyrock.

Through proper blast design and diligence in inspecting the geology before every blast, flyrock can readily be maintained within the quarry limits. It may be necessary to increase collars and adjust designs accordingly when blasting along the perimeter to accommodate the reduced deportation distance to receptors and to maintain flyrock within the property limits. The operational plan for the quarry has been designed to retreat towards the closest receptors thereby projecting flyrock and overpressures away from the receptors.



## TRANSMISSION AND HYDRO TOWERS

Transmission towers (Namely the Hydro One Corridor) runs parallel to the Southern limits of the proposed quarry licence noted on the proposed Operational Plan (refer to Appendix A). The MECP guideline for blast-induced vibration (12.5mm/s) does not apply to transmission/hydro towers as they are not classified as sensitive receptors. In order to safeguard the integrity of these structures, Hydro One has set a vibration limit of 50mm/s at the foundations of the transmission towers.

As per direction from Hydro One, calculations will be based on the 50mm/s limit. The tower shall be monitored for ground vibration and overpressure when vibration calculations suggest vibrations in excess of 35mm/s at the tower base. Based on the proposed Operations Plan for the Uppers Quarry, initial blasting operations are anticipated to be approximately 530m from the closest tower, however, will reach as close as 30m throughout the course of extraction at the Southern limits of Phase 1b and Phase 5.

Applying the equation from Predicated Vibration Limits at the Nearest Sensitive Receptor, for a distance of 530m (the conservative standoff distance to the transmission tower for the initial blasting) and a maximum explosives load per delay of 118kg (101mm diameter hole, 15m deep, 3m surface collar and 1 hole per delay), we can calculate the maximum PPV at the transmission tower for the initial blast as follows:

$$ppv = 1326 \left( \frac{530}{\sqrt{118}} \right)^{-1.38} = 6.2mm/s$$

The calculated 95% predicted PPV (based on the proposed blasting data discussed above) would be 6.2mm/s, well below the limit of 50mm/s. While this value resides below the 50mm/s threshold, it is anticipated that design modifications will be necessary to maintain compliance as the separation distance to some of the towers decreases and column loads increase. Fortunately, a variety of blast design alternatives are available to accomplish this including but not limited to reductions in blast hole diameter, change in explosives types, adjustment in bench heights and decking of holes.



## RESIDENTIAL WATER WELLS

Possible impacts to the water quality and production capacity of groundwater supply wells is a common concern for residents near blasting operations. Complaints related to changes in water quality often include the appearance of turbidity, water discolouration and changes in water characteristics (including nitrate, e-coli, and coliform contamination). Complaints regarding water production most often involve loss of quantity production, air in water and damage to well screens and casings. A review of research and common causes of these problems indicates that most of these concerns are not related to blasting and can be shown to be the direct impact of environmental factors and poor well construction and maintenance.

There is significant research and scientific substantiation demonstrating that outside of the immediate radius of approximately 20-25 blasthole diameters from a loaded hole, there is no permanent ground displacement resulting from a blast. As such, barring blasting activity within several meters of an existing well, the probability of damage to residential wells is essentially non-existent.

Despite the scientific support for the above conclusion, numerous studies have been performed to verify the validity of this statement. These studies have investigated the effects of blasting on varied well configurations and in varied geological mediums to permit conclusions to be readily extrapolated to diverse blasting operations. The conclusion of these studies has confirmed that with the exception of possible temporary increases in turbidity, blasting operations did not result in any permanent impact on wells outside of the immediate blast zone of the blast until vibrations levels reached exceedingly high intensities. Applying universally accepted threshold levels for ground vibrations eliminates the possibility for any long term adverse effects on wells in the vicinity of blasting operations.

In a study by Froedge (1983), blast vibration levels of up to 32.3mm/s were recorded at the bottom of a shallow well located at a distance of 60 meters (200 feet) from an open pit blast. There was no report of visible damage to the well nor was there any change in the water pumping flow rate. This study concluded that the commonly accepted limit of 50mm/s PPV level is adequate to protect wells from any damage. We reiterate, the current guideline limit for vibrations from quarry and mining operations is 12.5mm/s.

# EXPLOTECH

Rose et al. (1991) studied the effect of blasting in close proximity to water wells near an open pit mine in Nevada, USA. Blasts of up to 70 kilograms of explosives per delay period were detonated at a distance of 75 meters (245 feet) from a deep water well. There was no reported visible damage to the well. Fluctuations in water level and flow rate were evident immediately after the blast. However, the well water level and flow rate quickly stabilized.

The U.S. Bureau of Mines conducted a study (Robertson et al., 1990) to determine the changes in well capacity and water quality. This involved pumping from wells before and after nearby blasting. One experiment with a well in sandstone showed no change in well capacity after blasts induced PPV's at the surface of 84mm/s and there was no change in water level after PPV's of 141mm/s, well above the current guideline limit of 12.5mm/s.

Matheson et al. (1997) brought together available information on the most common complaints, the possible causes of the complaints and the relation between blasting and the complaint causes. This study yet again reaffirmed the fact that the attribution of well problems to blast sources are unfounded.

The MECP vibration limit of 12.5mm/s effectively excludes any possibility of damage to residential water wells. Based on available research and our extensive experience in Ontario quarry blasting, blasting at the Upper's Quarry will induce no permanent adverse impacts on the residential water wells on properties surrounding the site.



## BLAST IMPACT ON ADJACENT WATERCOURSES

The detonation of explosives in or near water can produce compressive shock waves which initiate damage to the internal organs of fish in close proximity, ultimately resulting in the death of the organism. Additionally, ground vibrations imparted on active spawning beds have the ability to adversely impact the incubating eggs and spawning activity. In an effort to alleviate adverse impacts on fish populations as a result of blasting, the Department of Fisheries and Oceans (DFO) developed the Guidelines for the Use of Explosives In or Near Canadian Fisheries Waters (1998). This publication establishes limits for water overpressure and ground vibrations which are intended to mitigate impacts on aquatic organisms while providing sufficient flexibility for blasting to proceed. Specifically, water overpressures are to be limited to 100kPa and, in the presence of active spawning beds, ground vibrations at the bed are to be limited to 13mm/s.

An existing watercourse currently runs in a North/South direction through the middle of Phase 3a and the Western sections of Phases 4 and 5. The operational plan has proposed for the realignment of the existing watercourse as part of the licence but will remain in its current location during blasting in Phases 1a and 1b. The operational plan shows the existing watercourse alignment, prior to its realignment, at an approximate 26m setback distance from all surrounding phases. Based on these separation distances and our experience on similar operations, water overpressures generated by the blasting will reside below the DFO 100kPa guideline limit and will have no impact on the adult fish populations present.

As per a preliminary document completed by Stantec, one of the fish species identified (Pike) in the adjacent watercourse have two (2) distinct spawning areas but technically anywhere that vegetation is flooded could be potential spawning habitat. The closest area of potential spawning lies approximately 208m from the initial Phase 1a (Mid Extraction Area) Sinking Cut Area blasting operations. The spawning time for the identified fish species in the adjacent watercourses has been established from March – July. As such, active spawning beds present would be subject to the DFO guideline vibration limit of 13mm/s. During spawning season, vibration monitoring will be required at the shoreline adjacent the closest spawning area on the blast side of the water body in order to confirm compliance with DFO limits for ground vibration.

Table 5 below is presented as initial guidance showing maximum permissible loads per delay based on various separation distances from spawning beds. The following maximum loads per delay are derived from the equation for ground vibrations listed earlier in this report and are based on a maximum vibration intensity of 13.0mm/s as experienced at the active spawning habitat:

Separation distance between possible spawning bed and closest borehole (meters)	Maximum recommended explosive load per delay (Kilograms)
500	305
450	245
400	195
350	150
300	110
250	75
200	49
150	27
100	12
75	6.5
50	3
30	1

**Table 5: Maximum Loads per Delay to Maintain 13.0mm/s at Various Separation Distances**

The generation of suspended solids within the watercourse as a result of the blasting activities will be negligible and grossly subordinate to suspended solids generated as a result of spring runoff and rain activity.



## **RECOMMENDATIONS**

It is recommended that the following conditions be applied for all blasting operations at the proposed Upper's Quarry:

1. An attenuation study shall be undertaken by an independent blasting consultant during the first 12 months of operation in order to obtain sufficient quarry data to confirm the initial guideline parameters and assist in refining future blast designs.
2. All blasts shall be monitored for both ground vibration and overpressure at the closest privately owned sensitive receptors adjacent the site, or closer, with a minimum of two (2) instruments – one installed in front of the blast and one installed behind the blast.
3. Blasts shall be designed to maintain vibrations below 13mm/s at the location of the closest identified active spawning bed as per DFO guidelines. When blasting during active spawning season, a minimum of one supplemental vibration monitor shall be installed on the shoreline closest to the spawning bed to confirm the vibration levels.
4. The guideline limits for vibration and water overpressure shall adhere to standards as outlined in the Guidelines For the Use of Explosives In or Near Canadian Fisheries Waters (1998) or any such document, regulation or guideline which supersedes this standard.
5. All blasts shall be monitored for ground vibration at the adjacent TC Energy High Pressure Natural Gas Pipeline when blasting within 100m of the pipeline or when calculations suggest vibrations in excess of 35mm/s.
6. Blasts shall be designed to maintain vibrations at the transmission towers in the Hydro One Corridor below 50mm/s or any such document, regulation or corporate policy in effect at the time. When vibration calculations suggest vibrations at the towers may exceed 35mm/s, the towers shall be monitored for ground vibration.
7. Blasts shall be designed to maintain vibrations at the 4832 Thorold Townline Road utility buildings below 50mm/s. When vibration calculations suggest vibrations at the utility buildings may exceed 35mm/s, the buildings shall be monitored for ground vibration.
8. The guideline limits for ground vibration and air overpressure shall adhere to standards as outlined in the Model Municipal Noise Control By-law



publication NPC 119 (1978) or any such document, regulation or guideline which supersedes this standard.

9. Orientation of the aggregate extraction operation will be designed and maintained so that the direction of the overpressure propagation will be away from structures as much as possible.
10. Blast designs shall be continually reviewed with respect to fragmentation, ground vibration and overpressure. Blast designs shall be modified as required to maintain compliance with current applicable guidelines and regulations.
11. Detailed blast records shall be maintained in accordance with current industry best practices.

The blast parameters described within this report are supported by the modelling in the attached appendices. As the quarry progresses and as site-specific data is collected from the on-going operation, the blast parameters can be refined, as necessary, to maintain continual compliance with MECP Guidelines.




## **CONCLUSION**

The blast parameters described within this report will provide a good basis for the initial blasting operations at this location. As site specific blast vibration and overpressure data becomes available, it will be possible to refine these parameters on an ongoing basis.

Blasting operations required for operations at the proposed Uppers Quarry site can be carried out safely and within governing guidelines set by the Ministry of the Environment, Conservations and Parks.

Modern blasting techniques will permit blasting to take place with explosives charges below allowable charge weights ensuring that blast vibrations and overpressure will remain minimal at the nearest receptors.



# Appendix A



- A. General**
- This Site Plan is prepared under the Aggregate Resources Act for a Class A Licence for a quarry below the ground water table.
  - Areas to be licensed: 103.6 ha. (±256.0 ac.)  
Areas to be extracted: 89.1 ha. (±220.2 ac.)
- B. References**
- Contour information was obtained from a topographic survey prepared by TEC Engineering (formerly Remshaw (Canada) Limited) using October 2016 and February 2017 aerial photography and is displayed in one metre intervals. Elevations shown are in metres above sea level (masl).
  - Topographic information was obtained from numerous sources including Ontario Geomatics (and Information Ontario), Google Earth Pro aerial photography captured on July 18, 2018 and field investigations for technical reports.
  - All topographic features and structures are shown to scale in Universal Transverse Mercator (UTM) with North American Datum 1983 (NAD83), Zone 17 (metre), Central Meridian 81 degrees west coordinate system.
  - Property boundaries were obtained from a Plan of Survey prepared by Matthew, Cameron, Heywood-Kerry T. Howe Surveying Ltd. dated April 5, 2012. Other property boundaries were established using Municipal Property Assessment Corporation (MPAC) parcel fabric data.
  - Zoning categories on or within 120 metres of the licence boundary are from the City of Niagara Falls Zoning Bylaw No. 79-200 (Schedules A3 and A4 - Consolidation April 2015) and the City of Thorold Zoning Bylaw No. 60-2019 (Schedules A8 and A13 - dated May 2019).
  - Land use information on or within 120 metres of the licence boundary has been compiled from October 2016 orthophotography, site visits and water well survey data.
- C. Groundwater**
- The maximum predicted water table is 184.9 masl and the contact aquifer potentiometric contours range between 176.0 and 184.9 masl (as per WSP's "Proposed Upper's Quarry - Maximum Predicted Water Table Report", dated October 2021).
- D. Drainage**
- Existing surface water drainage on and within 120 metres of the licence boundaries are by overland flow in the direction shown by arrows on the plan view.
- E. Site Access and Fencing**
- There are two (2) existing site accesses on Thorold Townline Road, six (6) existing site accesses on Upper's Lane, and three (3) existing site accesses on Beechwood Road.
  - Post and wire fencing (unless otherwise noted) exists in the locations shown on the plan view.
- F. Significant Features**
- All significant natural features on and within 120 metres of the licence boundary are shown on the Key Natural Heritage Features Schematic on this drawing.
  - All significant human-made features on and within 120 metres of the licence boundary are shown on the plan view.

- G. Aggregate Related Site Features**
- There are no existing aggregate operations or features within the licence boundaries such as stationary or portable equipment, stockpiles, recyclable materials, scrap, fuel storage, haul roads, berms or excavation faces.
- H. Technical Reports - References**
- Upper's Quarry, Acoustic Assessment Report, RWDI, August 2, 2023 January 11, 2024.
  - Agricultural Impact Assessment for Upper's Quarry, Colville Consulting Inc., October September 2021.
  - Upper's Quarry, Air Quality Assessment, RWDI Air Inc., July 12, 2023.
  - Archaeological Assessments:
    - Stage 1 Archaeological Resource Assessment of Walker Aggregates Proposed South Niagara Quarry, Part of Lots 102, 119, 120, 136 & 137, Archaeological Services Inc., December 2008.
    - Stage 1-2 Archaeological Assessment of Part 9764 Upper's Lane, Part of Lots 119 & 120, Archaeological Assessments Ltd., November 3, 2005.
    - Stage 2-3 Archaeological Assessment, Part of Lots 102, 119, 120, 136 & 137, Archaeological Assessments Ltd., November 21, 2012.
    - Stage 1-2 Archaeological Assessments, Upper's Quarry Additional Lands, Part of Lots 119, 120, Archaeological Assessments Ltd., April 20, 2020.
    - Stage 3 Mitigation of Development Impacts, Final Excavation Report, Walker XI (AgT-411), Upper's Quarry, Archaeological Research Associates Ltd., May 26, 2021.
    - Stage 4 Mitigation of Development Impacts, Final Excavation Report, Walker XI (AgT-178), Upper's Quarry, Archaeological Research Associates Ltd., July 22, 2021.
  - Blast Impact Analysis, Upper's Quarry, Exploitech, August 2023 April 2024.
  - Cultural Heritage Impact Assessment Report, Proposed Upper's Quarry, MHBC, October 2021.
  - Economic Benefits Analysis, Pstrm, February 2023 April 2024.
  - Level 2 Water Study Report and Response to JART Hydrogeological Comments, WSP, October 9, 2022.
  - Maximum Predicted Water Table Report, WSP, October 2021.
  - Upper's Quarry, Niagara, Level 1 and Level 2 Natural Environment Technical Report and Environmental Impact Study, Stantec, August 2023 April 2024.
  - Planning Justification Report and Summary Statement, MHBC, August 2023 April 2024.
  - Traffic Impact Study and TIS Addendum, Upper's Quarry, TYLin, March 23, 2023.
  - Visual Impact Assessment, Proposed Upper's Quarry, MHBC, October 2021 April 2024.

Key Natural Heritage Features Schematic



- Licence Boundary
  - Limit of Extraction
  - 120m Offset from Licence Boundary
  - Watercourse
  - Fish Habitat (offset for visual purposes)
  - Pike Spawning Habitat
  - Woodland
  - Non-Provincially Significant Wetlands (Evaluated)
  - Significant Wildlife Habitat - Mammals
  - MNRFP Mapped Deer-Wintering Congregation Area Significant Wildlife Habitat - Non-SAR But Habitat Seasonal Concentration Area
- Notes:
  - Added 120m offset from the licence boundary to the legend.
  - Added Woodland to the Key Natural Heritage Features Schematic.
  - Added Significant Wildlife Habitat - Mammals to the Key Natural Heritage Features Schematic.



- Legal Description**
- Part of Lots 119, 120, 136 & 137  
City of Niagara Falls (Geographic Township of Stamford)  
Regional Municipality of Niagara
- Licence Boundary
  - Limit of Extraction
  - Additional Lands Owned by License Applicant
  - Municipal Boundary
  - Contours with Elevation (Metres above sea level (MASL))
  - Public Road
  - Fence (1.2m post & wire fence unless otherwise noted)
  - Watercourse (Direction of flow indicated by arrows)
  - Surface Drainage Feature (Direction of flow indicated by arrows)
  - Water Feature
  - Wooded Area
  - 120m Offset From Licence Boundary
  - Parcel Fabric
  - Trans Canada Pipeline Easement
  - Hydro One Easement
  - Existing Site Access
  - Direction of Surface Drainage
  - Existing Culvert
  - Building/Structure
  - Cross Sections

Site Plan Acronyms

- ARA - Aggregate Resources Act
- MNRF - Ministry of Natural Resources and Forestry
- MHSTCI - Ministry of Heritage, Sport, Tourism and Culture Industries
- MECP - Ministry of the Environment, Conservation and Parks
- MGCS - Ministry of Government and Consumer Services
- DFO - Department of Fisheries and Oceans Canada
- ECA - Environmental Compliance Approval
- BMP - Best Management Practices Plan
- PTTW - Permit to Take Water
- MASL - Metres above sea level
- TCPL - Trans Canada Pipeline
- ROW - Right of way
- HMA - Hot mix asphalt
- PWQO - Provincial Water Quality Objectives
- MISA - Municipal Industrial Strategy for Abatement
- TS - Total Suspended Solids
- NCD - North Channel Design

Site Plan Amendments

No.	Date	Description	By

Site Plan Revisions (Pre-Licensing)

No.	Date	Description	By
1	January 2022	Added Key Natural Heritage Features Schematic and Section 'F' to the site plan notes	C.P.
2	August 2023	Updated site plan to incorporate JART and MNRF comments	C.P.
3	April 4, 2024	Updated site plan to incorporate JART and MNRF comments	C.P.

No.	Date	Description	By

**MHBC**  
PLANNING  
URBAN DESIGN  
& LANDSCAPE  
ARCHITECTURE  
113 COLLIER STREET, BARRE, ON, L4M 1H2 | P: 705.728.0045 F: 705.728.2010 | WWW.MHBCPLA.COM

**MHBC Stamp**  
Debra Walker  
Is authorized by the Ministry of Northern Development, Natural Resources and Forestry pursuant to Subsection 0.2(3)(f) of the Planning Act, R.S.O. 1990, Regulation 244/97 to prepare and certify site plans.

**MHBC Stamp**  
Christopher Poole  
Is authorized by the Ministry of Northern Development, Natural Resources and Forestry pursuant to Subsection 0.2(3)(f) of the Planning Act, R.S.O. 1990, Regulation 244/97 to prepare and certify site plans.

**Applicant**  
**walker aggregates**  
Walker Aggregates Inc.  
2800 Thorold Townline Road  
P.O. Box 100  
Thorold, Ontario  
L2V 3Y8

**Project**  
**Upper's Quarry**

MNRF Licence Reference No. \_\_\_\_\_ Applicant's Signature \_\_\_\_\_

Plan Scale: 1:3000 (Arch E) Date: **October 2021 April 4, 2024**

Drawn By: C.P. File No. **9811V**

Checked By: D.W.

File Name: **Existing Features**

Drawing No. **1 of 6**

File Path: N:\9811V - Walker Upper Quarry Drawings\Site Plan\CAD\9811V - Site Plan.dwg

A. General

- 1. Area to be licenced... 103.6 ha (256.0 ac)
2. Prior to the commencement of extraction operations, the licensee holder shall enter into an agreement with the appropriate road authority...

- 2.1. City of Niagara Falls
2.1.1. Road widening with a width of 2.94 metres along the entire length of frontage of the subject lands along Beechwood Road...
2.1.2. Road widenings are to be dedicated prior to the commencement of quarry operations.

- 2.2. The required entrance improvements, road improvements, and dedication of road widenings (to Thorold Townline Road, Beechwood Road and Uppers Lane) shall be completed to the satisfaction of the applicable road authorities...
3. The maximum amount of aggregate to be removed from this site in any calendar year is 1,800,000 tonnes.

B. Hours of Operation

1. The proposed quarry will have the following hours of operation:

Table with 4 columns: Activity, Monday to Friday, Saturday, Sunday. Rows include Drilling, extraction, blasting, aggregate processing, asphalt plant operations, etc.

C. Proposed Entrances/Exits and Fencing

- 1. For the Mid Extraction Area:
a. All traffic for extraction operations will enter and exit the Mid Extraction Area from Uppers Lane using a main entrance/exit in the location generally shown on the plan view.

D. Drainage and Siltation Control

- 1. Silt fencing/sediment control measures will be installed within the watercourse Realignment Transition Area prior to extraction in each extraction area and along the easterly and northerly limits of Phase 1B after the watercourse realignment is completed.

E. Site Preparation

- 1. All existing structures within the licence boundary shall be demolished or removed (and any associated residential entrances closed off) prior to extraction in each extraction area. Prior to erecting or demolishing a building, all necessary Permits shall be obtained by the City in accordance with the Ontario Building Code Act...
2. Timber resources (if any) will be salvaged for use as saw logs, fence posts and fire wood where appropriate.

F. Setbacks, Berms and Screening

- 1. Setbacks are as shown on the plan view. Excavation will occur within the extraction setback area along the west and northwest area of the licence boundary to accommodate grading required for the realignment of the existing watercourse. Furthermore, areas within the setbacks will be accessed as necessary to perform general site servicing, maintenance (berming, fencing etc.) and progressive rehabilitation. See Section N Variations from Control and Operation Standards on drawing 2 of 6.
2. Locations and heights for all acoustic/visual berms are provided on the plan view. All proposed berms shall be constructed in accordance with the 'Typical Acoustic Berm Detail' (on this drawing), 'Typical Visual Berm Detail' (on drawing 4 of 6) and, more specifically, berms adjacent to Beechwood Road shall be constructed in accordance with 'Typical Berm - Adjacent to Beechwood Road Detail' (on this drawing). Where the proposed berms transect the existing watercourse along the north perimeter, a culvert shall be installed in accordance with DFO requirements. Culverts will also be installed under berms, where necessary, to maintain existing drainage patterns from off-site and to the existing watercourse. All proposed berms will be vegetated with non-invasive plant species and maintained to control erosion. Temporary erosion control will be implemented as required.

G. Site Dewatering

- 1. Surface water will be discharged from the sump areas to the existing watercourse until the watercourse is realigned to the location of Phases 1B and 2B. Once the watercourse realignment has been completed, surface water will be discharged from the sumps to the realigned watercourse in Phase 1B.
2. Sump: During quarry development, a portable submersible pumps will be installed in each Initial Striking Cut Area for the purpose of dewatering to maintain a dry working area and/or aggregate washing. Water will be pumped from the sumps to a pond where it is either used for aggregate washing or discharged to the existing watercourse. The sumps shall be relocated (as required) within each excavation area during the operational life of the quarry.

H. Extraction Details

- 1. The extraction sequence is outlined on drawing 3 of 6.
2. The proposed maximum depth of extraction is indicated by the spot elevations shown on the plan view. Extraction shall proceed to a maximum depth of approximately 42 m below ground surface (ranging in elevation from 141 msl in the southwest to 149 msl in the northeast portions of the site), corresponding to the geologic base of the Gasport dolostone of the Lockport Group.
3. For the 'Watercourse Realignment Transition Area', the maximum depth of extraction is approximately 1 metre (down to an elevation of 174 msl) and any extraction in the 'Watercourse Realignment Transition Area' shall be completed as part of site preparation (construction of compensation ponds). No drilling or blasting shall be permitted in the 'Watercourse Realignment Transition Area'.
4. Internal haul road locations shall vary as extraction progresses and will be located on the quarry floor with the exception of at grade crossings.
5. Blasted aggregate will be transported back to the mobile crusher plant and processing area on the quarry floor for processing and shipping.

I. Equipment and Processing

- 1. A portable processing plant (including primary, secondary and tertiary crushing and screening units) will be permitted within the North and Mid Extraction Areas inclusive.
2. Processing shall be located within the limit of extraction and remain a minimum of 30 metres from the licence boundary and 90 metres from a property with a residential use.
3. All haulway trucks shall be directed to the haul route utilizing Thorold Townline Road from Uppers Lane and not directed to Beechwood Road from Uppers Lane.

- 3. During the sinking cuts and early phases of operation, the primary crusher will be integrated into a single processing plant located near the working face. In later phases, the primary crusher will split from the single integrated plant and start to follow the working face. The processing plant, which contains the secondary and tertiary crushers, shall be placed in the location identified on the Extraction Sequence Schematic on drawing 3 of 6 during each stage of extraction. The processing plant will be located at varying elevations, beginning at the top of rock during the sinking cut portion of operations, and moving to the final bench and then the final quarry floor as space becomes available. See note A.3. on drawing 4 of 6 for additional information.
4. Once processing has progressed to Phase 2A, a hot mix asphalt (HMA) batch plant facility shall be established on the quarry floor (in the location shown on the plan view) in Phase 1A. The HMA batch plant shall remain in the location shown on the plan view for the life of the quarry until extraction is complete and shall be removed during progressive rehabilitation.
5. In Phase 4, the portable processing plant shall require additional shielding in accordance with note A.5 on drawing 4 of 6.
6. A wash plant and temporary wash ponds may be established and located to move together with the portable processing plant, subject to permit approval from MCEP.
7. Equipment to be used onsite may include, but shall not be limited to:
a. Working Face - 1 inclined rock drill; 1 loader;
b. Processing - 1 portable processing plant including crushers, screeners, and stackers; 2 loaders (at stockpiles);
c. Asphalt - 1 asphalt plant; 2 loaders; 1 compressor; vent; 1 dust controller blower (motor and stack); elevator motor; conveyor motor; oven motor; pug mill (door and motor);
d. Conveyor(s);
e. Generator(s) (diesel-fueled); and
f. Rock trucks, haul trucks, shipment trucks and fuel trucks.
8. Wash ponds(s) and sump(s) may be permitted in accordance with Environmental Compliance Approval or Permit to Extract Water Resource Material. The pond(s) and sump(s) will move throughout operations and as extraction progresses horizontally and vertically.
9. Equipment used for construction of the perimeter berms/barriers, overburden stripping, rehabilitation, the new watercourse corridor, as well as other quarry related construction projects will be utilized on site.

J. Frequency / Timing of Blasts

- 1. Prior to blasting being permitted within the 300 metre setback of the Trans-Canada Pipeline, identified as 'TransCanada Blasting Buffer Area' on this Plan, the licensee shall address the requirements of notes D.5 on drawing 4 of 6.
2. All blast monitoring reports shall be retained by the licensee for a period of seven years after each blast and made available upon request for audit purposes. See Section D on drawing 4 of 6 for detailed blasting requirements.

K. Fuel Storage

- 1. Fuel storage tanks will be located in close proximity to the main processing plant (or in an alternative location subject to approval by the MNRF). Fuel storage tanks shall be installed and maintained in accordance with Technical Standards and Safety Act, 2000, Liquid Fuels Handling Code, 2000 and Liquid Fuels Regulation Reg. 21/01.
2. All fuel tanks shall be double sided or placed in containment facilities large enough to hold the tanks maximum volume.
3. Fuel trucks shall be used to transfer fuel to on-site equipment in accordance with the Liquid Fuels Handling Code, 2000.
4. A Spills Contingency Plan shall be prepared and implemented prior to site preparation. The Spills Contingency Plan shall be available on site, submitted to the City of Niagara Falls Fire Services Department and all employees and contractors shall be informed and required to comply with this plan. The location of on site fire routes, as well as any other emergency operation plans for the quarry, will be included in this plan.

L. Spills Plan

- 1. In case of an accidental spill of petroleum products, the following contingency plan will be activated:
a. The Ministry of Environment, Conservation and Parks (MECP) (see address and phone number below) and surrounding landowners will be notified.
b. For a leakage or spill, immediate action will be taken to stop it. At the same time, measures will be taken to prevent spreading. These measures may include building a berm or construction of a ditch, for instance.
c. The quarry operator shall commence recovery procedures by collecting the spilled substance into containers.
d. The soil in the area affected by the spill or leak shall be removed and disposed of at a location prescribed by the MECP.

M. Scrap and Recycling

- 1. Scrap may be stored on-site and shall be removed on an on-going basis.
2. Scrap shall only include material generated directly as a result of the aggregate operation such as refuse, debris, scrap metal, lumber, discarded machinery, equipment and motor vehicles.
3. All fluids shall be drained from any discarded equipment, machinery or motor vehicle prior to storage and disposed of in accordance with the Environmental Protection Act.
4. Scrap shall not be stored within 30 metres of any body of water or the licence boundary and shall be kept in close proximity to the main processing plant.
5. Recycling of asphalt, concrete, porcelain and glass shall be permitted on-site.
6. Recyclable asphalt materials shall not be stockpiled within:
6.1. 30 metres of any waterbody or man-made pond; or
6.2. 2 metres of the ground water table.
7. Recyclable material shall be kept in close proximity to the main processing plant and shall be stored separately on the quarry floor and within the extraction area limit.
8. Ruber or other structural metal shall be separated from recyclable aggregate material during processing and placed in a designated scrap pile on-site which shall be removed on an on-going basis.
9. Recycled aggregate shall be removed on an on-going basis.
10. Recycling activities shall not interfere with the operational phases of the site or with rehabilitation.
11. Once the site is depleted, no further importation of recyclable material shall be permitted.
12. Once final rehabilitation has been completed and approved in accordance with the site plan, all recycling operations shall cease.
13. The site shall be kept in an orderly condition.

N. Variations from Control and Operation Standards

Table with 4 columns: No., Variation, Rationale, Standard (if 13). Rows describe setbacks, berms, and site preparation variations.

O. Trans Canada Pipeline (TCP)

- 1. The licensee shall notify TCP. If it intends to blast within 300 metres of their right-of-way (easement), No blasting shall occur until written consent is obtained from TCP.
2. Any other work (other than blasting) within 30 metres of TCP's right-of-way requires written consent from TCP.
3. Crossing the TCP right-of-way with vehicles is not permitted without written consent from TCP.
4. No material extraction shall be permitted within 49.30 metres of TCP's right-of-way without written consent from the Canada Energy Regulator (CER) formerly NEB or National Energy Board.
5. No buildings or structures shall be constructed anywhere on TCP's right-of-way. Permanent buildings and structures shall be located a minimum of 7 metres from the edge of the TCP's right-of-way. Temporary or accessory buildings shall be located a minimum of 3 metres from the edge of the right-of-way.
6. A minimum setback of 7 metres from the nearest portion of a TCP's pipeline right-of-way shall also apply to any parking area or loading area, including any parking spaces, loading spaces, stacking spaces, bicycle parking spaces, and any associated drive aisle or driveway.





Table 1: Sensitive Receptors Within 500m of the Licence Boundary. Columns include Receptor, Address, Distance, and Receptor details.

Legal Description

Part of Lots 119, 120, 136 & 137 City of Niagara Falls (Geographic Township of Stamford) Regional Municipality of Niagara

Legend section containing symbols and descriptions for Licence Boundary, Limit of Extraction, Additional Lands Owned by Licensee Applicant, Municipal Boundary, Contours with Elevation, Public Road, Fence, Watercourse, Surface Drainage Feature, Watercourse - Re-aligned, 100 Year Floodline, Water Feature, Wooded Area, Woodland Mitigation and Enhancement Area, Watercourse Realignment Transition Area, 120m Offset From Licence Boundary, Trans Canada Blasting Buffer Area, Parcel Fabric, Trans Canada Pipeline Easement, Hydro One Easement, Entrance / Exit, Limited Service Access, Gate, Culvert, General Direction of Excavation & Boundary, Berm, Building/Structure, Spot Elevation, Cross Sections.

Site Plan Acronyms

- 1. ARA - Aggregate Resources Act
2. MNRF - Ministry of Natural Resources and Forestry
3. MHSTCI - Ministry of Heritage, Sport, Tourism and Culture Industries
4. MECP - Ministry of the Environment, Conservation and Parks
5. MGCS - Ministry of Government and Consumer Services
6. DFO - Department of Fisheries and Oceans Canada
7. ECA - Environmental Compliance Approval
8. BMP - Best Management Practices Plan
9. PTTW - Permit to Take Water
10. MASL - Metres above sea level
11. TCPL - Trans Canada Pipeline
12. ROW - Right of way
13. HMA - Hot mix asphalt
14. PWQO - Provincial Water Quality Objectives
15. MISA - Municipal Industrial Strategy for Abatement
16. TSS - Total Suspended Solids
17. NCD - North Channel Design

Site Plan Amendments

Table with 4 columns: No., Date, Description, By. Shows amendment 1 on 2022-01-20 and amendment 2 on 2023-08-02.

Site Plan Revisions (Pre-Licensing)

Table with 4 columns: No., Date, Description, By. Shows revision 1 on 2023-01-20 and revision 3 on 2024-04-04.

MHBC Stamp and Planning Urban Design & Landscape Architecture logo with contact information for Debra Walker and Christopher Poole.

Applicant

walker aggregates logo and address: Walker Aggregates Inc., 2800 Thorold Townline Road P.O. Box 100 Thorold, Ontario L2V 3Y8.

Project

Upper's Quarry

MNRF Licence Reference No.

Applicant's Signature: Christopher Poole, Date: October 2021 April 4, 2024

Plan Scale: 1:3000 (Arch'E), Date: October 2021 April 4, 2024, Drawn By: C.P., File No.: 9811V

File Name

Operational Plan

Drawing No.

2 of 6

**A. General**

- This plan depicts a schematic operations sequence for the property based on the best information available at the time of preparation.
- Phases do not represent any specific or equal time period.
- The direction of extraction will be in accordance with the General Direction of Excavation (shown on the plan view) unless otherwise authorized by MNR. Notwithstanding the operational and rehabilitation notes, demand for certain products, blending of materials or Water Study Contingency measures may require minor deviations in the extraction and rehabilitation sequence. Any major deviations from the operations sequence shall require approval from the MNR. The maximum combined disturbed area which includes the processing plant, berms, stockpiles, silt pond, active extraction area and area being stripped for the next area of extraction within the licence boundary identified on this Drawing but excludes the area of Phase 1A needed for the continued operation of the asphalt plant for the life of the quarry. Concurrent extraction of phases is permitted for blending purposes provided the overall maximum combined disturbed area does not exceed 40 hectares to ensure progressive rehabilitation of the site is being undertaken as required by the Site Plans.
- Progressive and final rehabilitation will be completed in direct correlation to the development of the quarry as the extraction limits are reached and enough area is available to ensure that rehabilitation activities will not interfere with the production, stockpiling and processing of aggregate materials.

**B. Initial Site Preparation**

- A Conservation Easement shall be placed on the lands identified as Woodland Mitigation Planting Areas (off-site) that are situated outside of the licence area and such Easement shall be registered on the lands prior to the commencement of Phase 1 (1A and 1B) to secure protection of the lands for conservation purposes in perpetuity.
- Generally, site preparation in Phases 1 and 2 to include but not limited to:
  - Constructing the main entrance and cross over(s) in accordance with entrance permit approvals
  - Establishing fencing around licenced boundary (see Section N Variations from Control and Operation Standards on drawing 2 of 6)
  - Removal of trees and existing buildings (in accordance with all site plan requirements and applicable regulations)
  - Proceed with stripping of overburden/topsoil from Phase 1 and, if necessary, Phase 2
  - Construction of berms/acoustic barriers within the perimeter setback of the licence boundary (as shown on the plan view)
- Initial plantings in Woodland Mitigation Planting Area (off-site) in accordance with the Rehabilitation Plan. Off-site plantings will be completed in the Woodland Mitigation Planting Areas (off-site) prior to the removal of the woodcut soil of the unopened road allowance in Phases 1A and 1B.
- Install water management and erosion and sediment control measures (silt fencing) in accordance with note D.1 on this drawing and note E.1.e on drawing 4 of 6.
- Commence portable crushing/screening plant set up. The plant shall operate in accordance with Section A on drawing 4 of 6 for all Phases.

**C. Phase 1 (1A and 1B)**

- Commence extraction in the 'Initial Sinking Cut Area' identified in the Mid and South Extraction Area (see plan view for location).
- Phase 1A shall be extracted in up to three (3) lifts to a depth ranging between 140 masl and 145 masl.
- Phase 1B shall be extracted in one (1) to two (2) lifts to a depth ranging between 142 masl in and 147 masl.
- A portable pump shall be utilized as necessary in the Mid Extraction Area and the South Extraction Area to discharge water to a man-made pond for aggregate washing or to a sediment forebay before being discharged to the existing watercourse. During heavy rainfall events (25 mm or more), the pump will be deactivated as necessary to prevent flooding along the watercourse downstream of the site. The discharge pond and forebay locations will move with the quarry face until the final quarry depth is reached in each extraction area. At this point, a permanent sump will be established in each extraction area.
- During Phase 1, a new watercourse channel shall be constructed along the east side of Thorold Townline Road (within Phase 1B) for the eventual realignment of the existing watercourse. As resource extraction is completed in Phase 1B, this area will be filled with clay overburden material from on-site to an elevation ranging between 173 to 178 masl. The new watercourse and riparian wetland channel shall be constructed, designed and vegetated in accordance with DFO's authorization and this Rehabilitation Plan (drawing 5 of 6).
- As extraction reaches the final quarry floor, and there is sufficient separation from the quarry floor working areas in Phase 1A, a 2:1 adioslope along the easterly and northerly limit of Phase 1B shall be backfilled with either: (i) overburden stockpiled on-site; (ii) overburden in Phase 2; or (iii) material imported from Licence Numbers 11175 and 4437 (subject to drawing 5, note C.7) or with overburden in Phase 4.
- Commence site preparation of Phase 2.

**D. Phase 2 (2A & 2B)**

- Commence extraction in the 'Initial Sinking Cut Area' identified in the North Extraction Area (see plan view for location).
- Phase 2A shall be extracted in up to three (3) lifts to a depth ranging between 141 masl to 145 masl.

- Phase 2B shall be extracted in one (1) to two (2) lifts to a depth of 155 masl.
- A portable pump shall be utilized as necessary to discharge water to a man-made pond for aggregate washing or to a sediment forebay before being discharged to the existing watercourse. During heavy rainfall events (25 mm or more), the pump will be deactivated as necessary to prevent flooding along the watercourse downstream of the site. The discharge pond and forebay locations will move with the quarry face until the final quarry depth is reached. At this point, a permanent sump will be established.
- Similar to Phase 1, the new watercourse channel shall be constructed within Phase 2 running along the east side of Thorold Townline Road (Phase 2B) for the eventual realignment of the existing watercourse. As resource extraction is completed in Phase 2B, this area will be filled with clay overburden material from on-site to an elevation ranging between 173 to 178 masl. The new watercourse and riparian wetland channel will be constructed, designed and vegetated in accordance with DFO authorization and Rehabilitation Plan (drawing 5 of 6).
- As extraction reaches the final quarry floor, and there is sufficient separation from the quarry floor working areas in Phase 2A, a 2:1 adioslope along the easterly and northerly limit of Phase 2B shall be backfilled with either: (i) overburden stockpiled on-site; (ii) overburden in Phase 3B; or (iii) either material imported from Licence Numbers 11175 and/or 4437 (subject to drawing 5, note C.7) or with overburden in Phase 4.
- Commence site preparation of Phase 3.

**E. Phase 3 (3A & 3B)**

- Proceed with stripping of overburden/topsoil.
- Prior to undertaking any works within Phase 3A that may result in any serious harm to fish, according to 35(1) of the Fisheries Act, the Licensee shall obtain a Fisheries Act Authorization from the Department of Fisheries and Oceans (DFO) and shall fulfill any other conditions required by the DFO as stated on its authorization. Once obtained, a copy of the Fisheries Act Authorization shall be provided to the MNR. Once the watercourse has been realigned to the satisfaction of DFO, stripping of overburden and topsoil can proceed in Phase 3A.
- In the event that watercourse relocation has not been approved or completed, extraction in Phase 3B may proceed before extraction in Phase 3A.
- In the event that Phase 3B is extracted before Phase 3A, a portable pump shall be utilized as necessary to discharge water to a man-made pond for aggregate washing or to a sediment forebay before being discharged to the existing watercourse. During heavy rainfall events (25 mm or more), the pump will be deactivated as necessary to prevent flooding along the watercourse downstream of the site. The discharge pond and forebay locations will move with the quarry face until the final quarry depth is reached. At this point, a permanent sump will be established.
- Phase 3A and 3B shall be extracted in up to three (3) lifts to a depth ranging between 145 masl to 149 masl. Extraction will proceed in an easterly direction, moving gradually from north to south.
- Once the existing watercourse has been realigned, stripping and extraction in Phase 3A may proceed.
- Complete progressive rehabilitation of new watercourse and riparian wetland channel in accordance with Rehabilitation Plan (drawing 5 of 6).
- Continue progressive rehabilitation of the quarry perimeter where limits of extraction have been reached and there is sufficient separation from the quarry floor working areas.
- Commence site preparation of Phase 4.

**F. Phase 4**

- Proceed with stripping of overburden/topsoil.
- Commence Phase 4 extraction in an easterly direction, moving gradually from north to south.
- Phase 4 shall be extracted in up to three (3) lifts to a depth ranging between 142 masl in and 147 masl.
- Continue progressive rehabilitation of the quarry perimeter where limits of extraction have been reached and there is sufficient separation from the quarry floor working areas.

**G. Phase 5**

- Proceed with stripping of overburden/topsoil.
- Commence Phase 5 extraction in an easterly direction, moving gradually from north to south.
- Phase 5 shall be extracted in up to three (3) lifts to a depth ranging between 140 masl and 143 masl.
- Continue progressive rehabilitation of the quarry perimeter where limits of extraction have been reached and there is sufficient separation from the quarry floor working areas.


**H. Final Phase**

- Complete extraction of any remaining resource in the extraction limit near the entrance in Phase 1A and 1B (e.g. ramp).
- As part of the final operations of the site, remove office/scale house and scales, asphalt plant, recycled asphalt material and any other equipment and scrap from the site.
- Continue and complete with final rehabilitation of the site. Complete quarry face backfilling on the remaining quarry faces as identified on drawing 5 of 6.

**Extraction Sequence Schematic**  
Scale 1:7500



Off-site plantings to be initiated as part of Site Preparation and completed prior to Phase 1  
 Undisturbed  
 Site Preparation  
 Under Extraction  
 Progressive and Final Rehabilitation



**Legal Description**

Part of Lots 119, 120, 136 & 137  
 City of Niagara Falls (Geographic Township of Stamford)  
 Regional Municipality of Niagara

**Legend**

	Licence Boundary		120m Offset From Licence Boundary
	Limit of Extraction		Trans Canada Blasting Buffer Area - See Note D.3 on drawing 4 of 6
	Additional Lands Owned by Licensee Applicant		Parcel Fabric
	Municipal Boundary		Trans Canada Pipeline Easement
	Contours with Elevation Metres above sea level (MASL)		Hydro One Easement
	Public Road		Entrance / Exit
	Fence 1.2m post & wire fence unless otherwise noted		Limited Site Access For Phases 1A, 1B and 5 in South Extraction Area
	Watercourse Direction of flow indicated by arrows		Gate
	Surface Drainage Feature Direction of flow indicated by arrows		Culvert
	Watercourse - Realigned (Status: 2025)		General Direction of Excavation & Boundary
	100 Year Floodline		Berm Top - House Allocation Berm Bottom - Visual Berm
	Water Feature		Building/Structure
	Wooded Area		Spot Elevation Metres above sea level (MASL) Top - Existing Bottom - Maximum Depth of Extraction
	Woodland Mitigation and Enhancement Area (off-site)		Cross Sections A1
	Watercourse Realignment Transition Area		

- Site Plan Acronyms**
- ARA - Aggregate Resources Act
  - MNR - Ministry of Natural Resources and Forestry
  - MHSTCI - Ministry of Heritage, Sport, Tourism and Culture Industries
  - MECP - Ministry of the Environment, Conservation and Parks
  - MGCS - Ministry of Government and Consumer Services
  - DFO - Department of Fisheries and Oceans Canada
  - ECA - Environmental Compliance Approval
  - BMP - Best Management Practices Plan
  - PTTW - Permit to Take Water
  - MASL - Metres above sea level
  - TCPL - Trans Canada Pipeline
  - ROW - Right of way
  - HMA - Hot mix asphalt
  - PWQO - Provincial Water Quality Objectives
  - MISA - Municipal Industrial Strategy for Abatement
  - TSS - Total Suspended Solids
  - NCD - North Channel Design

**Site Plan Amendments**

No.	Date	Description	By

**Site Plan Revisions (Pre-Licensing)**

No.	Date	Description	By
1	January 2022	Revised note C.1 and hatched watercourse realignment area.	C.P.
2	August 2023	Updated site plan to incorporate JART and MNR comments	C.P.
3	April 4, 2024	Updated site plan to incorporate JART and MNR comments	C.P.

**MHBC**  
 PLANNING  
 URBAN DESIGN  
 & LANDSCAPE  
 ARCHITECTURE  
 113 COLLIER STREET, BARRE, ON, L4M 1H2 | P: 705.728.0405 F: 705.728.2010 | WWW.MHBCPLAN.COM

**MHBC Stamp**  
 Debra Walker  
 Is authorized by the Ministry of Northern Development and Forestry pursuant to Subsection 0.2(3)(f) of Ontario Regulation 609/04 to prepare and certify site plans.

**MHBC Stamp**  
 Christopher Poole  
 Is authorized by the Ministry of Northern Development and Forestry pursuant to Subsection 0.2(3)(f) of Ontario Regulation 609/04 to prepare and certify site plans.

**Applicant**  
  
 Walker Aggregates Inc.  
 2800 Thorold Townline Road  
 P.O. Box 100  
 Thorold, Ontario  
 L2V 3Y8

**Project**  
**Upper's Quarry**

**MNR Licence Reference No.** \_\_\_\_\_ **Applicant's Signature** \_\_\_\_\_

**Plan Scale:** 1:3000 (Arch E) **Date:** October 2021 April 4, 2024

**Drawn By:** C.P. **File No.:** 9811V

**Checked By:** D.W.

**File Name:** Extraction Sequence

**Drawing No.:** 3 of 6

**File Path:** N:\09\9811V - Walker Upper's Quarry\Drawings\Site Plan\CAD\9811V - Site Plan.dwg

A. Acoustic Assessment

- 1. Minimum 3 metre tall acoustic berms shall be constructed in the locations shown on the plan view.
2. The acoustic berms shall be constructed during site preparation and prior to extraction.
3. The primary crusher shall stay within 30 metres of the working face to maximize shielding effect of the quarry terrain, except when extraction is in the South Extraction Area as per note A.4 below.
4. Material extracted from the South Extraction Area shall be processed in the Mid Extraction Area.
5. While processing in Phase 4, the licensee shall maintain a 6 metre tall barrier at a radius of 40 metres to the southeast of the processing plant's secondary crushers (see plan view for location). The barrier shall be made of material stockpiles, noise walls, or a combination of both. The barrier shall extend long enough to shield receptors R4 and R5 (see plan view) from the secondary crushers. If a barrier needs to be removed for operational reasons, the barrier must be extended to block the additional line-of-sight to both R4 and R5. The 40 metre radius from the barrier to the processing plant's secondary crushers must also be maintained.
6. All construction practice shall meet the sound emission standards defined in MECP Publication NCP-115.
7. The following best practice measures shall be undertaken to minimize the potential for construction noise impacts related to site preparation, berm creation and rehabilitation but not related to extraction and processing activities:
a. Construction will be limited to time periods allowed by the City's applicable bylaws. If construction activities are required outside of these hours, the licensee will seek permits from the City in advance.
b. All internal combustion engines will be fitted with appropriate muffler systems.
c. The licensee's operating procedures will contain a provision that any initial complaint will trigger verification that the general noise control measures agreed to on this Plan are in effect.
d. In the presence of persistent noise complaints, all construction equipment will be verified to comply with MECP's NCP-115 guidelines.
e. In the event of verified presence of persistent noise complaints and subject to the results of a field investigation, alternative noise control measures, reasonably available, in selecting appropriate noise control and mitigation measures, consideration will be given to the technical, administrative and economic feasibility of the various alternatives.

B. Air Quality

- 1. The licensee shall apply water or another provisionally approved dust suppressant to internal haul roads and processing areas, as necessary, to mitigate dust.
2. Processing equipment shall be equipped with dust suppressing or collection devices, where the equipment creates dust and is operating within 300 metres of an air quality sensitive receptor (as set out in the Air Quality Impact Assessment).
3. The licensee shall obtain an environmental compliance approval under the Environmental Protection Act whereas required to carry out operations at the quarry.
4. The site will operate in accordance with the Best Management Practices Plan (BMP) for Fugitive Dust Emissions. The BMP may be amended from time to time, considering actual impacts and operational considerations. The incorporation of changes in the BMP are based on the maximum daily production rates. At lower production rates, the control measures specified in the BMP can be reduced accordingly, provided dust remains mitigated on site.
5. The following mitigation measures shall be incorporated into the BMP:
a. Blasting operations occurring within 300 metres of a residential receptor shall have a smaller blast area, not exceeding 200 m<sup>2</sup> in area.
b. Aggregate extraction, processing and shipping does not exceed 9,000 tonnes per day.
c. Under dry conditions, the capacity to apply water on an hourly basis to all traveled haul roads within the licence boundaries is required.

C. Archaeology

- 1. Areas identified as "Archaeological Site - Protected Areas Requiring Further Archaeological Assessment" on this drawing reflect areas that require further archaeological assessment and are protected by a 20 to 30 metre protective buffer. A 30 metre protective buffer is also identified on this drawing.
2. No ground alterations including overburden stripping and excavation, or development of any kind shall occur within areas identified as "Archaeological Site - Protected Areas Requiring Further Archaeological Assessment" and their respective protective buffers until:
a. the required investigations are completed in accordance with the Stage 1 and 2 Archaeological Assessment prepared by Archaeological Research Associates Ltd. (April 2020),
b. any recommendations that the respective sites have no further cultural heritage value or interest are made as a result of completing further investigations, and
c. the associated reports are entered into the Ontario Public Register of Archaeological Reports and copies are provided to the MNRF.
3. Should the required investigations noted above determine that any portion of the "Protected Areas Requiring Further Archaeological Assessment" contain significant archaeological resources that will require long term protection, the licensee shall amend the drawings to remove areas to be protected as set out by the associated reports on the Site Plan accordingly.
4. Until note C.3 has been satisfied, a temporary barrier shall be established around the perimeter of each "Archaeological Site - Protected Areas Requiring Further Archaeological Assessment" as shown on this drawing as per the following:
a. All soil disturbing activities within the 50 metre monitoring buffers shall be monitored by a licensed archaeologist to ensure the effectiveness of the avoidance strategy. The archaeologist shall ensure that the temporary barrier is in the appropriate location and shall be empowered to stop construction if there is a concern for impacts to an archaeological site. No go! instructions shall be issued to all work crews for the protected areas, and the locations of the protected areas shall be shown on all appropriate contract drawings. The protected areas shall be inspected by a licensed archaeologist once the strategy is no longer required, and the effectiveness of the strategy shall be reported to the MNRF.
5. Immediately upon issuance of the License, and once the construction schedule has been finalized, a licensed archaeologist will be retained by the licensee so that monitoring can occur where required. The remaining archaeological fieldwork will be completed upon issuance of the license by the MNRF.
6. Should deeply buried archaeology remains be found during the course of site preparation and/or extraction activities, the licensee shall immediately contact both the MHSTCI and Registrar or Deputy Registrar of the Cemeteries Regulation Unit of the Ministry of Government and Consumer Services (MGCS).
7. In the event that human remains are encountered during construction or extraction activities, the licensee shall immediately contact both the MHSTCI and Registrar or Deputy Registrar of the Cemeteries Regulation Unit of the Ministry of Government and Consumer Services (MGCS).

D. Blasting

- 1. An attenuation study shall be undertaken by an independent blasting consultant during the first 12 months of operation in order to obtain sufficient quarry data to confirm the initial predictive parameters and assist in refining future blast designs.
2. All blasts shall be monitored for both ground vibration and overpressure at the closest privately owned sensitive receptors adjacent to the site, or closer, with a minimum of two (2) instruments - one installed in front of the blast and one installed behind the blast.
3. Blasts shall be designed to maintain vibrations below 130mm/s at the location of the closest identified active spawning bed as per DFO guidelines. When blasting during active spawning season, a minimum of one supplemental vibration monitor shall be installed on the shoreline closest to the spawning bed to confirm the vibration level.
4. The guideline limits for vibration and water overpressure shall adhere to standards as outlined in the Guidelines For the Use of Explosives In or Near Canadian Waters (1998) or any such document, regulation or guideline which supersedes this standard.
5. All blasts shall be monitored for ground vibration at the adjacent Trans Canada Energy High Pressure Natural Gas Pipeline when blasting within 100m of the pipeline or when calculations suggest vibrations in excess of 35mm/s.
6. Blasts shall be designed to maintain vibrations at the transmission towers in the Hydro One Corridor below 50mm/s or any such document, regulation or corporate policy in effect at the time. When vibration calculations suggest vibrations at the towers may exceed 35mm/s, the towers shall be monitored for ground vibration.
7. Blasts shall be designed to maintain vibrations at the 4832 Thorold Townline Road utility buildings below 50mm/s. When vibration calculations suggest vibrations at the utility buildings may exceed 35mm/s, the buildings shall be monitored for ground vibration.
8. The guideline limits for ground vibration and the overpressure shall adhere to standards as outlined in the Model Municipal Noise Control By-law publication NCP 119 (1978) or any such document, regulation or guideline which supersedes this standard.
9. Orientation of the aggregate extraction operation shall be designed and maintained so that the direction of the overpressure propagation will be away from structures as much as possible.
10. Blast designs shall be continually reviewed with respect to fragmentation, ground vibration and overpressure. Blast designs shall be modified as required to maintain compliance with current guidelines and regulations.
11. Detailed blast records shall be maintained in accordance with current industry best practices.

E. Natural Heritage

- 1. General
a. Existing vegetation within the setbacks shall be maintained except where berms, haul roads and conveyors are required.
b. A monitoring program of all berm plantings, rehabilitation plantings and berm mitigation and enhancement plantings shall be prepared in consultation with regulatory authorities to address replacement plantings if die off occurs and to confirm viable conditions have been established.
c. New vegetation shall be maintained in accordance with note G.5 on this drawing.
d. Prior to construction, all fencing and sediment control measures shall be installed and implemented prior to and during construction at the easterly limit of Phases 1A and 2A where field drainage enters the existing watercourse. This may include the use of all fencing, check dams, straw bales, riprap and/or other techniques as required depending on slope, nature and location. Silt fencing will serve to demarcate the limit of protected area until the watercourse is diverted.
e. Stockpiling of all excavated material shall be in accordance with note H.7 on drawing 2 of 6.
2. Topsoil and overburden stockpiles shall be maintained in accordance with the Best Management Practices for the Protection, Creation and Maintenance of Bank Swallow Habitat (MNRF 2017). Stripped overburden and topsoil for reclamation shall be utilized in accordance with notes E.4, E.5 and E.6 on drawing 2 of 6.
3. Dust control will be implemented in accordance with Section B on this drawing.
4. Fuel storage shall be in accordance with the notes under Section K on drawing 2 of 6.
5. Side slopes steeper than 3:1 shall be seeded with a naturalizing mix of native, non-invasive wildflowers and grasses capable of rapid germination and growth to stabilize slopes and minimize erosion and maintenance.
2. Natural Channel Design
a. The existing watercourse will remain open (not culverted) where it enters the south limit of the South Extraction Area.
b. Where the watercourse exits the North Extraction Area, a culvert will be installed to maintain the watercourse while allowing an acoustic berm to be constructed. As part of final rehabilitation, the berm and culvert shall be removed to allow for the watercourse to be open.
c. As part of site preparation, a compensation pond will be constructed in the Watercourse Realignment Transition Area within Phase 2B, in accordance with the Natural Channel Design Report (Stantec 2021). The compensation pond will be excavated to a maximum depth of 174 mm in this area and in accordance with DFO authorization. No siting or blasting shall occur in this Transition Area.
d. An extraction is completed in Phases 1B and 2B, these areas will be filled with clay overburden material to an elevation ranging between 173 to 175 m asl in accordance with the Natural Channel Design Report (Stantec 2021). A new watercourse channel will be constructed, vegetated and designed in these areas and will include the following design elements:
1. Floodplain wetlands
2. Fish habitat ponds, including native pike spawning habitat as well as foraging, spawning and rearing habitat for other fish species
3. Creek sections
4. Wood debris tree protection and wood reinforced berms
5. Log sills
6. Augmented riffle
e. Culverts will be installed under Upper's Lane and the unopened road allowance.
f. 2:1 side slopes shall be established on the east side of the new watercourse channel down to the quarry floor.
g. Once the realigned watercourse channel has been constructed in Phases 1B and 2B and adequate vegetation to mitigate potential erosion has been established (as confirmed by an ecologist), water from the existing watercourse will be diverted to the realigned watercourse in consultation with regulatory authorities. A fish rescue net shall be undertaken prior to dewatering and channel reclamation. A License to Collect Fish for Scientific Purposes will be obtained for the fish rescue.
h. The Natural Channel Design (NCD) Report details the Rehabilitation Planting Plan drawings L-460 to L-463 and L-500 to L-503.

F. Woodland and Terrestrial Habitat Enhancement

- 1. The 20 ha woodland situated on the east side of Thorold Townline Road shall be removed during the advancement of operations in Phase 1A/1B. Tree clearing in the woodland shall be undertaken outside of the breeding bird period and the active bat season from March 23<sup>rd</sup> and August 26<sup>th</sup>.
2. The lands identified off-site as "Woodland Compensation Mitigation and Enhancement Area" on this drawing, an area of 4.3 ha, shall be planted in accordance with the Rehabilitation Plan (Drawing 5 of 6 and 6 of 6) and Rearing Plan (drawing L-460 and L-500 to L-503 from the NCD Report.
3. The lands identified on-site as "Deciduous Woodland - Broad Deciduous Swamp and Swamp-Thicket / Marsh Meadow" on drawing 6 of 6, an area of 4.1 ha, shall be planted in accordance with the Rehabilitation Plan.
4. Planning for the off-site Woodland Compensation Mitigation and Enhancement Area will commence in the appropriate planting season following license approval.

G. Woodland and Wildlife Habitat Compensation Plan

- 1. The goal of the on-site Rehabilitation, in particular, the detailed planting plan that accompanies the NCD and the off-site Woodland Mitigation and Enhancement Area (see drawing 5 of 6, Table 1) shall be refined in consultation with regulatory authorities to ensure that woodland and wildlife habitat compensation objectives shall be preserved in accordance with regulatory authorities. (i) allow practices and management responses to changing forest conditions in the Woodland Compensation Mitigation and Enhancement Areas such as pest infestations, climatic conditions, (ii) species selection) and restoration ecology; and (iii) achieve a net gain in the ecological functions of the local and regional landscape through:
d.1. Increasing the total area of woodland cover in the regional landscape.
d.2. Improving associated landscape functions such as vegetative linkages and native flora distribution.
d.3. Improving forest ecological characteristics such as species diversity, age class distribution and structural diversity, while retaining native genetics through seed collection and replanting. For example, prior to the removal of the existing 2 ha woodland:
d.3.1. Establish the planting of the 0.7 ha of off-site Woodland Mitigation and Enhancement Area woodland approximately 4.5 to 6 months prior to woodland planting.
d.3.2. Tree seeds and nuts shall be gathered from the woodland for direct planting in the Woodland Compensation Mitigation and Enhancement Areas to promote the continuity of local genetic stock and a similar community composition to the removed vegetation community (FODCO).
d.3.3. Leaf litter and seeds containing native understory vegetation will shall be translocated to promote rapid establishment of a healthy forest soil microbiome; and
d.3.4. Transplanting of native saplings and small shrubs from the woodland to the off-site Woodland Mitigation and Enhancement Areas compensation planting areas, where feasible.
d.4. Incorporating specific wildlife habitat features for bats, deer and other wildlife, such as bat roosting structures (bat boxes or coritols), conifer tree clusters for cover, browse tolerant shrubs and mast producing trees.
d.5. Incorporating specific planting in setbacks and the watercourse realignment channel. For example, plantings that provide habitat for moorhens including common milkweed (Asclepias syriaca), swamp milkweed (Asclepias incarnata) and reed producing plants.
4. Significant Wildlife Habitat and Wildlife
a. Vegetation clearing where milkweed plants are present will shall proceed when monarch larvae are absent (September 30<sup>th</sup> to April 1<sup>st</sup>).
b. The setbacks along Thorold Townline Road and Beechwood Road shall be planted with a mix of deciduous and coniferous trees and shrubs with a range of sizes as per the Visual Recommendations on this drawing. Native plant material that is complementary to the regional and local landscape shall be used (see Rehabilitation Plan drawing 5 of 6, planting plan drawings L-460 to L-463 and L-500 to L-503 from the NCD Report for additional information).
c. Eight mulchbarrel bait boxes shall be installed in the NCD corridor where creek and vernal pool habitat is created.
5. Fish and Fish Habitat
a. Implement notes D.3 and D.4 on this drawing.
b. Water shall be discharged from the sump area to the existing watercourse until water flow is diverted to the watercourse realignment channel. Once the watercourse realignment has been completed, water shall be discharged from the sump locations to the realigned watercourse. Pumping and discharge shall occur as required to support fish habitat.
c. Water collected from the sump area shall be directed to a holding pond for storage to allow for settling of suspended solids and dispersion of other constituents such as hydrogen sulfide and alkalinity. Following this pond treatment, water will be discharged to the existing watercourse until water flow is diverted to the watercourse realignment channel. Once the watercourse realignment has been completed, water shall be discharged from the holding pond to the realigned watercourse. Pumping and discharge shall occur as required to support fish habitat.
d. Create riparian corridor to provide pike spawning habitat as shown on the rehabilitation plan, drawing 5 of 6.
6. Wetlands
a. Wetlands along the existing watercourse will shall be maintained until the watercourse has been diverted to the watercourse realignment channel.
b. Once the watercourse has been diverted, the created wetlands created in the watercourse realignment channel shall be maintained.
7. Monitoring Program
a. A monitoring plan shall be prepared in consultation with regulatory authorities to assess the performance of the watercourse realignment and to confirm that impacts to wildlife habitat are not occurring as a result of dewatering.
b. A monitoring program of all woodland mitigation and enhancement plantings shall be prepared in consultation with regulatory authorities to confirm viable conditions have been established.
c. A trigger mechanism and contingency plan, as detailed in WSP's Level 2 Water Study Report, shall be implemented upon license approval to proactively ensure natural heritage features and their functions are maintained (i.e. fish habitat, wetland habitats downstream and at 500m Beechwood Road, and woodlands) during operational and rehabilitation phases.
d. A Wetland Monitoring Program shall be prepared in consultation with regulatory authorities and shall be implemented to monitor the reconfigured wetland features to accurately monitor any changes in the wetland community over time and to measure the success of the re-configuration / restoration and management actions. Long-term monitoring sites and/or monitoring transects shall be established to include a count of the number of stems and percent cover for all plant species present. Monitoring shall be conducted annually at a similar time of year (i.e. late July) for the duration of Phase 1A through Phase 3A.
e. All lands identified as part of the Wetland Monitoring Program shall be categorized by the wetland index based on the Floristic Quality Assessment System for Southern Ontario.
f. The results of the Wetland Monitoring Program shall be submitted to the MNRF and all appropriate agencies, as determined by MNRF, annually prior to December 31<sup>st</sup> until the re-alignment and rehabilitation is complete. It is recommended that, at a minimum, a 5-year monitoring plan be undertaken upon completion of the wetland re-configuration plantings.

H. Traffic

- 1. Prior to commencement of extraction operations, the required entrance improvements, road improvements and realignment of road watercourses (to Thorold Townline Road, Beechwood Road and Upper's Lane) shall be completed to the satisfaction of the appropriate regulatory authorities (the Regional Municipality of Niagara and the City of Niagara Falls) and in full and general accordance with the signed "Thorold Upper's Lane Conceptual Intersection Design" and "Upper's Lane Vehicle Movement Diagram" provided on this drawing 6 of 6.


I. Visual

- 1. Where possible and to the extent to which it is present, existing vegetation located along the site perimeter within the setback area shall be retained.
2. 3.0 metre high acoustic berms and 2.4 metre high visual berms shall be established in the locations shown on the plan view. Berms shall be constructed in a manner, using native material, that provides a natural appearance. Berms shall be seeded with a naturalizing mix of wildflowers and grasses to stabilize slopes and minimize erosion and maintenance.
3. Within the "Extended Planting Area" (as shown on this drawing), trees shall be planted at a spacing of 5 to 10 metres on centre, depending on species. Where possible, plantings shall be randomly spaced and staggered up on the berm to one third of its maximum height to appear more natural. Plantings shall also extend a minimum of 3 metres out from the berm towards the road where available space permits. All vegetation shall be selected for wind, soil and erosion control and/or otherwise native. Native, non-invasive species that complement the existing surroundings shall be utilized.
4. Where "Large Planting Stock" is indicated (see plan view "Extended Planting Areas" and "Typical Visual Berm Detail" on this drawing), the area shall be planted with deciduous trees of minimum 40 centimetres height, coniferous trees of minimum 1.5 metre in height, and shrub species of minimum 40 centimetres height.
5. Where "Small Planting Stock" is indicated (see plan view "Extended Planting Areas" and "Typical Visual Berm Detail" on this drawing), the area shall be planted with deciduous trees of minimum 20 centimetres in height (or bare root stock when in season). Planting shall occur for 40 metre stretches on either side of Upper's Lane and the unopened road allowance facing Thorold Townline Road and on either side of the internal entrance off of Upper's Lane. The large planting stock shall be planted 3 metres beyond the berm and small planting stock shall extend from the toe of the berm by 2 metres up the berm.
6. See "Planting Cell Detail for Planted Berms" and "Planting Cell Detail for at Grade Planting" on this drawing for additional information.
Planting cells for berms may include, but shall not be limited to the following:
Trees
White Pine
White Spruce
Sugar / Silver Maple
White Birch
Common Hothobby
Paper Birch
Trembling Aspen
Basswood
White Pine
Eastern Hemlock
Balsam Fir
American Larch
White Pine
Shrubs
Staghorn Sumac
American Elder
Nannyberry
Common Nettlebarb
Common Chokecherry
Highbush Cranberry
4. To ensure survival and positive growth rate, the vegetative screening shall be maintained as an effective visual screen over time. Allowance of natural succession is encouraged.
5. During the first year planted trees and shrubs shall be watered and monitored until established. After the first year and up to five years, trees shall be inspected biannually (end of a vegetation of Year 1 and end of Year 4). Trees or shrubs which are in poor condition at the time shall be fertilized, watered and monitored to improve their health and vigor.
6. A mortality rate of up to 15% of all trees planted over the course of the five year maintenance period is expected. Trees that die exceeding this percentage shall be replaced yearly, preferably in the spring or early summer. If the dieback or decline or trees occur via direct views into the Quarry, these trees shall be replaced even if there is a die off rate below 15% of all trees.



J. Water Study

- 1. A long term monitoring program will be implemented during the quarry operation and rehabilitation phases, until stable conditions are observed after quarry decommissioning.
2. In the event a well interference claim is received, the licensee shall implement the following mitigation plan to protect the local groundwater users.
a. Prior to extraction, landowners shall be provided with a copy of the water well interference plan as well as the contact information for the licensee and MECP (Wells Help Desk: 1-888-386-9355 or email: wellshelpdesk@ontario.ca).
b. If a water well interference claim is received by the licensee the following actions shall be taken:
1. The licensee shall immediately notify MNRF and MECP of the complaint.
2. The licensee shall contact a well contractor in the event of a well malfunction and residents will be provided a temporary water supply within 24 hours, if the issue cannot be easily determined and rectified.
3. The well contractor shall contact the resident with the supply issue to resolve the problem as expeditiously as possible, provided the resident authorizes the contractor.
4. If the issue raised by the landowner is related to loss of water supply, the licensee shall have a qualified hydrogeologist / well contractor determine the likely causes of the loss of water supply, which can result from a number of factors, including pump failure (owner's expense) (pumped operation), loss of well maintenance / well dewatering (owner's expense) or lowering of the water level in the well from the quarry development (licensee expense). This assessment process shall be carried out at the expense of the licensee and the licensee shall continue to supply water at their expense until the problem is rectified. The licensee shall be responsible for restoring the water supply by replacing the well or providing a water treatment system. The licensee is responsible for the expense to restore the water quality.
5. If it has been determined that the quarry caused the water supply interference (i.e., lowering of the water level), the licensee shall continue to supply water at their expense until the problem is rectified. The following mitigation measures shall be considered, and the appropriate measure(s) implemented at the expense of the licensee:
1. Adjust pump pressure;
2. Lowering of the pump to take advantage of existing water storage within the well;
3. Deepening of the well to increase the available drawdown, if the well deepening changes the water quality or water treatment shall be required;
4. Widening of the well to increase the available storage of water;
5. Relocation of the well to another area on the property; or
6. Drilling multiple wells.
f. If the issue raised by the landowner is related to water quality, the licensee shall have a qualified hydrogeologist / well contractor determine the likely causes of the change in water quality, and water monitoring results from the quarry and background monitoring results from the baseline well survey to determine if there is any potential correlation with the quarry. If it has been determined that the quarry caused a water quality issue, the licensee shall continue to supply water at their expense until the problem is rectified. The licensee shall be responsible for restoring the water supply by replacing the well or providing a water treatment system. The licensee is responsible for the expense to restore the water quality.
3. A split action plan shall be carried out in accordance with the notes in Section N.1 Splits Plan on drawing 2 of 6.
4. A trigger mechanism and contingency plan as set out in WSP's Level 2 Water Study Report shall be implemented.
5. WSP's Water Study Report confirms that drawdown impacts do not extend to areas identified in the Niagara Peninsula Source Protection Plan as Intake Protection Zones.

PLANTING CELL DETAIL FOR PLANTED BERMS



PLANTING CELL DETAIL FOR AT GRADE PLANTING



Legal Description

Part of Lots 119, 120, 136 & 137 City of Niagara Falls (Geographic Township of Stamford) Regional Municipality of Niagara

Legend table listing symbols for Licence Boundary, Limit of Extraction, Additional Lands Owned by Licensee Applicant, Municipal Boundary, Contours with Elevation, Public Road, Fence, Watercourse, Surface Drainage Feature, Watercourse - Re-aligned, 100 Year Floodline, Water Feature, Wooded Area, Watercourse Realignment Transition Area, Woodland Compensation Mitigation and Enhancement Area, Archaeological Site, and Archaeological Offset.

Site Plan Acronyms

- 1. ARA - Aggregate Resources Act
2. MNRF - Ministry of Natural Resources and Forestry
3. MHSTCI - Ministry of Heritage, Sport, Tourism and Culture Industries
4. MECP - Ministry of the Environment, Conservation and Parks
5. MGCS - Ministry of Government and Consumer Services
6. DFO - Department of Fisheries and Oceans Canada
7. ECA - Environmental Compliance Approval
8. BMP - Best Management Practices Plan
9. PTTW - Permits to Take Water
10. MASL - Metres above sea level
11. TCPL - Trans Canada Pipeline
12. ROW - Right of way
13. HMA - Hot mix asphalt
14. PWQC - Provincial Water Quality Objectives
15. MISA - Municipal Industry Program for Abatement
16. TSS - Total Suspended Solids
17. NCD - North Channel Design

Site Plan Amendments

Table with columns for No., Date, Description, and By, showing no amendments.

Site Plan Revisions (Pre-Licensing)

Table with columns for No., Date, Description, and By, showing three revisions related to watercourse realignment and site plan updates.

MHBC logo and contact information for Planning Urban Design & Landscape Architecture.

Draft stamp and signatures of Debra Walker and Christopher Poole, authorized by the Ministry of Natural Resources and Forestry.

Walker Aggregates Inc. logo and contact information.

Project: Upper's Quarry

Table for MNR Licence Reference No. and Applicant's Signature.


Table for Plan Scale (1:3000 Arch E) and Date (October 2021 April 4, 2024).

Table for File Name (Report Recommendations) and Drawing No. (4 of 6).





Table for File Path (N:\049811V - Walker Upper Quarry Drawings\Site Plan\CAD\811V - Site Plan.dwg).

Moved traffic details to drawing 5 of 6 due to limited space

Typical Visual Berm Detail N.T.S.



Extended Planting Areas Scale 1:3000



Note: The existing vegetation shall be maintained within the three metre setback from the licence boundary (where applicable) if feasible.

**PROGRESSIVE REHABILITATION**

- A. General**
- Area calculations:
    - a. Licenced area: **103.6 ha**
    - b. To be extracted: **89.1 ha**
    - c. Final rehabilitation within licence (total): **103.6 ha**
  - c.a. Lake: **66.6 70.0 ha**
  - c.b. Shoreline wetland: **1.3 ha**
  - c.c. Wetland/pond/stream: **2.9 ha**
  - c.d. Terrestrial and Vegetated Slopes: **22.7 19.4 ha**
  - c.e. Deciduous Woodland & Vegetated Screening: **4.2 6.1 ha**
  - c.f. **Treed Deciduous Swamp**: **2.9 ha**
  - c.g. **Swamp-Thicket & Marsh Meadow**: **0.9 ha**
  - c.h. Undisturbed: **3.9 ha**

d. To be rehabilitated outside of licence: **47.6 ha**

    - d.a. Woodland Compensation Area: **47.6 ha**

2. The maximum predicted water table is 184.9 msl and the contact aquifer potentiometric contours ranges between 178.0 and 184.9 msl (see WSP's "Proposed Upper's Quarry - Maximum Predicted Water Table Report", dated October 2021).

**B. Phasing**

- As excavation reaches the limit of extraction or maximum depth, progressive rehabilitation shall commence.
- Progressive rehabilitation shall follow the general direction and sequence of extraction identified on the plan view and described in the notes on drawing 3 of 6. Minor deviations in operational/rehabilitation sequence will be permitted in order to adjust for any variable resources not marked conditions. Any major deviations from the operations sequence shall require approval from the MNR.
- Prior to extraction commencing in Phases 3A and 3B, side sloping adjacent to Phases 1B and 2B shall be completed to allow for the existing watercourse realignment to be finalized.
- Dewatering of the quarry will ultimately discharge to the watercourse (pre and post realignment). The quarry will continue dewatering operations to maintain a dry quarry floor. When the rock is fully extracted, it is proposed that dewatering operations will cease and the quarry will be permitted to fill naturally with surplus precipitation, surface water and any contribution from groundwater seepage to form a lake. As shown on the plan view, shallow shoreline wetland areas shall be created to provide aquatic habitat.

**Watercourse Realignment Channel Area**

- As portions of the watercourse realignment channel are identified as riparian habitat, the channel shall be planted according to the requirements of each respective planting zone: (i) riparian planting zone; (ii) upland planting zone; (iii) shoreline planting seeding zone and (iv) the lake staking planting zone. Details relating to construction, planting and monitoring requirements for the watercourse realignment corridor are contained within the "Natural Channel Design Report" prepared by Stantec Consulting Ltd. (dated October 2021 April 2024).

**6.2. The on-site Woodland Compensation Mitigation and Enhancement Area includes the areas identified as the Deciduous Woodland on the plan view of this drawing - Treed Deciduous Swamp and Swamp-Thicket/Marsh Meadow. To these areas shall be no less than 4.9 4.5 ha in total area.**

Plantings in these areas are set out in Tables 1 to 3 on this drawing and the Natural Channel Design Report planting plan drawings L-460 to L-463 and L-500 to L-503 respectively. In the Deciduous Woodland (on-site), additional conifer species will be added to the species mix to provide additional screening.

**A woodland and wildlife habitat compensation/rehabilitation plan shall be prepared in consultation with regulatory authorities in accordance with Note E-5.8 E.3.0 on drawing 4 of 6.**

**C. Slopes and Grading**

- Progressive rehabilitation will utilize a variety of rehabilitation techniques including:
  - a. backfilling extraction faces and quarry floors; or
  - b. leveling extraction faces vertical
2. Excess soil, as defined in Ontario Regulation 244/97 may be imported to this site to facilitate the following rehabilitation:
  - 2.1. To establish the final elevations, slopes and grades depicted on the plan view
  - 2.2. To top dressing to establish vegetation
3. Liquid soil, as defined in Ontario Regulation 406/19 under the Environmental Protection Act, is not authorized for importation to the site.
4. The quality of excess soil imported to the site for final placement must be equivalent to or more stringent than the applicable excess soil quality standards as determined in accordance with Ontario Regulation 244/97, as amended from time to time, and must be consistent with the site conditions and the end use identified in the approved rehabilitation plan.
5. Where a qualified person is retained or required to be retained in accordance with Ontario Regulation 244/97, the quality, storage, and final placement of excess soils shall be done according to the advice of the qualified person.

**6. Excess soil imported to facilitate rehabilitation as described on this site plan shall be undertaken in accordance with Ontario Regulation 244/97 under the Aggregate Resources Act, as amended from time to time.**

7. The cumulative total amount of excess soil that may be imported to this site for rehabilitation purposes is 2,400,000 750,000 m<sup>3</sup>.

**8. The final rehabilitated landforms established using the rehabilitation techniques will consist of a lake, shoreline wetlands, riparian corridor, woodlands, gradually sloping grades, 2/1 and 3/1 side slopes, and vertical faces as shown on the plan view.**

**D. Seeding and Planting**

- Side slopes steeper than 3:1 shall be seeded with a naturalizing mix of native, non-invasive wildflowers and grasses capable of rapid germination and growth to stabilize slopes and minimize mowing and maintenance.
- The deciduous woodlands, **reed-deciduous swamp**, **swamp-thicket/marsh meadow**, shoreline wetland, and realigned watercourse channel (riparian corridor) shall be planted with species identified in Tables 1-4 on this drawing and the "Natural Channel Design Report" planting plan drawings L-460 to L-463 and L-500 to L-503 respectively.

**E. Drainage**

- Final surface drainage will follow the rehabilitated contours and directional arrows shown on the plan view.
- Once the quarry is depleted, pumping will cease and portions of the site below the ground water table will fill with water.
- The quarry dewatering discharge will be directed to the watercourse (pre and post alignment) and ultimately flow to Beaversdam Creek to support fish habitat and downstream wetlands.
- The licensee shall operate in accordance with the conditions of the MECP, PTTW and ECA for the ongoing dewatering of the site.

**F. Trigger Mechanism and Contingency Plan**

- During progressive rehabilitation, until surrendering the licence, the licensee is required to operate in accordance with the Trigger Mechanism and Contingency Plan outlined below.
- The monitoring program will allow a comparison of observed conditions throughout the quarry development to baseline conditions. The predicted effects of the quarry have been reviewed and are based on the numerical groundwater model simulations and baseline water quality. Should the observed quarry effects differ from those predicted, a trigger mechanism has been developed to trigger the implementation of appropriate contingency measures to mitigate impacts before they occur. The quarry dewatering discharge will be directed to the Existing Watercourse, and ultimately flow to Beaversdam Creek. The discharge water will consist of a mixture of direct precipitation and groundwater inflows from the contact aquifer, shallow bedrock aquifer, deep bedrock aquifer and likely a small contribution from the underlying low aquifer. The ratio of groundwater contribution from each unit is related to the relative hydraulic conductivities. Based on the hydraulic testing conducted as part of this study, it is interpreted that the majority of the groundwater inflow will originate from the shallow bedrock unit. Therefore, it is predicted that the quarry discharge will have similar water quality to the shallow bedrock aquifer baseline ranges. The observed 2019 pumping test discharge water quality, which is predicted to be similar to the future quarry discharge water quality, supports this interpretation.
- Monthly sampling of the quarry sump discharge has been included in the monitoring program, for the analysis of parameters with an associated Provincial Water Quality Objectives (PWQO), as well as selected parameters which aid in the assessment of influence from the various bedrock units. The trigger mechanism for the sump discharge to the Existing Watercourse is to assess the monthly sump water quality results against the list of trigger concentrations summarized in the table below.

Parameter	Proposed Trigger Mechanism	Applicable Standard
pH (pH units)	6.5 - 8.5	PWQO / MISA
TSS	25	MISA
Hydrogen Sulphide (Undissociated)	0.002	PWQO
Total Oil and Grease	No visible sheen or odour	PWQO

Note: Trigger concentrations in mg/L unless otherwise noted.

- The shallow bedrock aquifer groundwater is more mineralized / harder than the surface water in the vicinity of the Site. However, it satisfies the PWQO for most parameters. The two exceptions are undissociated hydrogen sulphide and total phosphorus. A trigger for hydrogen sulphide has been included in the trigger mechanism for quarry discharge. In the case of total phosphorus, the median total phosphorus concentration in the baseline surface water quality currently exceeds the PWQO, making the Existing Watercourse a Policy 2 receptor for this parameter. It is predicted that the total phosphorus concentration in the future quarry discharge will be below that of the upstream surface water in the Existing Watercourse. As such, total phosphorus has not been included in the trigger mechanism.
- The Municipal Industrial Strategy for Abatement (MISA) was also considered, as such, pH, total suspended solids (TSS) and total oil and grease have also been included in the trigger mechanism.
- The monthly sump discharge sample results shall be compared with the background conditions in the Existing Watercourse (station SW3) and Beaversdam Creek (station SW1). If parameter concentrations in the sump discharge exceed the above trigger concentrations without a corresponding exceedance in the background surface water, then weekly sampling of the quarry sump shall be initiated. Weekly sampling will continue until less than two parameter concentrations in the sump discharge exceed the trigger concentrations.
- If weekly sampling is required for a period of more than four (4) weeks, contingency measures shall be implemented to reduce concentrations in the quarry discharge. Trigger exceedances for pH, TSS and total oil and grease would initiate a review of the design and operation of the quarry discharge sump. Where required, improvements shall be made to reduce discharge concentrations.

- At existing pits and quarries within southern Ontario, hydrogen sulphide is typically not routinely included in the trigger mechanism. In southwestern Ontario, where the bedrock geology can favour hydrogen sulphide in groundwater, an Effluent Objective for hydrogen sulphide has been included in site ECA. A sump or holding pond with a large surface area normally allows enough off-gassing of the hydrogen sulphide to meet the Effluent Objective. For the quarry, the need for sufficient off-gassing of hydrogen sulphide shall be taken into consideration during the design and construction of the internal ditch network and sump pond for the Site. It is anticipated that the hydrogen sulphide concentration in the discharge to the Existing Watercourse will be lower than the PWQO / trigger concentration as a result of the off-gassing. If the hydrogen sulphide concentration in the discharge are found to consistently exceed the trigger once the operational phase of the quarry begins, then a review of the design and operation of the internal ditch network and sump pond shall be completed with the objective of increasing the rate of off-gassing prior to discharge. Additional measures, such as aeration of the pond, may also be employed to enhance the off-gassing of hydrogen sulphide.

**FINAL REHABILITATION**

**G. General**

- All equipment and buildings/structures shall be removed from the licenced areas.
- Field/property access points may be established to access the site for maintenance and monitoring purposes. All operational access points shall be decommissioned and fenced as part of final rehabilitation.
- The long term average surface water and lake level elevation is estimated to be approximately 175.15 msl.
- At final rehabilitation, outflow from the realigned watercourse and the quarry lake will continue to discharge from the licence area at the present location where the existing watercourse channel crosses the northern licence boundary.

**Table 1**

UPLAND PLANTING ZONE:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
BP	15%	105	Betula papyrifera	Paper Birch	125	2 Gal. Pot
CAO	5%	105	Carya ovata	Hickory	100	2 Gal. Pot
GP	10%	210	Quercus prinus	Pignut Hickory	100	2 Gal. Pot
JN	15%	315	Juglans nigra	Black Walnut	250	15 Gal. Pot
PI	15%	150	Pinus strobus	White Pine	150	2 Gal. Pot
POA	15%	210	Populus grandidentata	Largetooth Aspen	175	10 Gal. Pot
QA	15%	315	Quercus alba	White Oak	250	15 Gal. Pot
QAL	10%	210	Quercus alba	White Oak	175	10 Gal. Pot
SAS	5%	105	Sassafras albidum	Sassafras	100	5 Gal. Pot
TA	10%	210	Tilia americana	Basswood	175	10 Gal. Pot
Totals:	100%	2107	Upland Zone Planting Density Target Goal = 8 trees / 100 m <sup>2</sup>			
SHRUBS:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
EA	15%	82	Echinacea americana	Grey Dogwood	50	2 Gal. Pot
EV	15%	82	Hamamelis virginiana	Common Witch-hazel	50	3 Gal. Pot
PIA	15%	82	Prunella americana	American Plum	100	2 Gal. Pot
RI	15%	82	Rhus typhina	Staghorn Sumac	80	3 Gal. Pot
RS	15%	82	Rosa rugosa	Rose	80	2 Gal. Pot
VI	15%	82	Viburnum lentago	Nannyberry	50	3 Gal. Pot
Totals:	100%	428	Riparian Zone Planting Density Target Goal = 10 shrubs / 100 m <sup>2</sup>			
RIPARIAN PLANTING ZONE:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
AF	20%	87	Acer x freemanii	Freeman Maple	250	10 Gal. Pot
PI	15%	44	Pinus strobus	White Pine	150	2 Gal. Pot
QB	15%	66	Quercus bicolor	Swamp White Oak	175	10 Gal. Pot
QAL	20%	87	Quercus alba	White Oak	250	10 Gal. Pot
SAG	10%	44	Sax. angustifolia	Peachleaf Willow	100	2 Gal. Pot
SAN	10%	44	Sax. nigra	Black Willow	200	3 Gal. Pot
Totals:	100%	438	Riparian Zone Planting Density Target Goal = 1 tree / 100 m <sup>2</sup>			
UPLAND FOREST PLANTING ZONE:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
BP	5%	158	Betula papyrifera	Paper Birch	125	2 Gal. Pot
CAO	5%	158	Carya ovata	Hickory	100	2 Gal. Pot
GP	10%	316	Quercus prinus	Pignut Hickory	100	2 Gal. Pot
JN	15%	474	Juglans nigra	Black Walnut	250	15 Gal. Pot
PI	15%	158	Pinus strobus	White Pine	150	2 Gal. Pot
POA	15%	316	Populus grandidentata	Largetooth Aspen	175	10 Gal. Pot
QA	5%	158	Quercus alba	White Oak	250	15 Gal. Pot
QAL	10%	316	Quercus alba	White Oak	175	10 Gal. Pot
SAS	5%	158	Sassafras albidum	Sassafras	100	5 Gal. Pot
TA	5%	158	Tilia americana	Basswood	175	10 Gal. Pot
Totals:	100%	3160	Upland Forest Zone Planting Density Target Goal = 10 trees / 100 m <sup>2</sup>			
RIPARIAN FOREST PLANTING ZONE:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
AF	10%	236	Acer x freemanii	Freeman Maple	250	10 Gal. Pot
PI	15%	236	Pinus strobus	White Pine	150	2 Gal. Pot
QB	15%	236	Quercus bicolor	Swamp White Oak	175	10 Gal. Pot
QAL	15%	236	Quercus alba	White Oak	250	10 Gal. Pot
SAG	10%	118	Sax. angustifolia	Peachleaf Willow	100	2 Gal. Pot
SAN	10%	118	Sax. nigra	Black Willow	200	3 Gal. Pot
VI	10%	118	Viburnum lentago	Nannyberry	50	3 Gal. Pot
Totals:	100%	1786	Riparian Forest Zone Planting Density Target Goal = 10 trees / 100 m <sup>2</sup>			
DENSE UPLAND PLANTING ZONE:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
PT	20%	41	Populus tremuloides	Trembling Aspen	150	3 Gal. Pot
QA	20%	41	Quercus alba	White Oak	250	15 Gal. Pot
GA	20%	41	Quercus alba	White Oak	250	15 Gal. Pot
TA	20%	41	Tilia americana	Basswood	175	10 Gal. Pot
Totals:	100%	204	Dense Upland Zone Planting Density Target Goal = 3 trees / 100 m <sup>2</sup>			
LIVESTAKE PLANTING ZONE:						
Sym.	Percent	Quantity	Botanical Name	Common Name	Ht. (cm)	Root
COB	10%	276	Comus renzosa	Red Ostrer Dogwood	min. 75	Livestake
SAC	10%	276	Sax. discolor	Livestake	min. 75	Livestake
SAE	10%	276	Sax. rigida	Livestake	min. 75	Livestake
SAP	10%	276	Sax. perfoliata	Livestake	min. 75	Livestake
Totals:	100%	1104	Livestake Zone Planting Density Target Goal = 35 live stakes / 100 m <sup>2</sup>			



**Legal Description**

Part of Lots 119, 120, 136 & 137  
City of Niagara Falls (Geographic Township of Stamford)  
Regional Municipality of Niagara

**Legend**

- Licence Boundary
- Limit of Extraction
- Contours with Elevation (Metres above sea level (MASL))
- Public Road
- Trans Canada Pipeline Easement
- Hydro One Easement
- Extraction Face (Above Water - Red, Below Water - Orange)
- Entrance / Exit
- Gate
- Culvert
- Fence (5m post & wire fence unless otherwise noted)
- Building/Structure
- Proposed Floor Elevation (Metres above sea level (MASL))
- Proposed Final Grade
- Cross Sections

**Legend - Cross Sections**

- Licence Boundary
- Limit of Extraction
- Existing Grade - Undisturbed
- Existing Grade - Removed / Altered
- Maximum Predicted Water Table (See Note A.2 on this drawing)
- Quarry Floor / Face
- Backfilled
- Lake or Pond
- Hydro Corridor

**Site Plan Amendments**

No.	Date	Description	By
1	January 2022	Revised notes C.3 and G.1. Added notes C.2, C.4 and C.5.	C.P.
2	August 2023	Updated site plan to incorporate JART and MNR comments	C.P.
3	April 4, 2024	Updated site plan to incorporate JART and MNR comments	C.P.

**Site Plan Revisions (Pre-Licensing)**

No.	Date	Description	By
1	January 2022	Revised notes C.3 and G.1. Added notes C.2, C.4 and C.5.	C.P.
2	August 2023	Updated site plan to incorporate JART and MNR comments	C.P.
3	April 4, 2024	Updated site plan to incorporate JART and MNR comments	C.P.

**MHBC PLANNING URBAN DESIGN & LANDSCAPE ARCHITECTURE**

113 COLLIER STREET, BARRIE, ON, L4M 1H2 | P. 705.728.0405 | F. 705.728.2010 | WWW.MHBCAN.COM

**MHBC Stamp** Debra Walker  
 It is authorized by the Ministry of Northern Development, Forestry and Natural Resources pursuant to Ontario Regulation 244/97 to prepare and certify site plans.

**MHBC Stamp** Christopher Poole  
 It is authorized by the Ministry of Northern Development, Forestry and Natural Resources pursuant to Ontario Regulation 244/97 to prepare and certify site plans.

**Walker aggregates**

Walker Aggregates Inc.  
2800 Thorold Townline Road  
P.O. Box 100  
Thorold, Ontario  
L2V 3Y8

**Project: Upper's Quarry**

**MNR Licence Reference No.** Applicant's Signature

**Plan Scale:** 1:3000 (Arch E) **Date:** October 2021 April 4, 2024


**Drawn By:** C.P. **File No.:** 9811V

**Checked By:** D.W.


**File Name:** Rehabilitation Plan

**Drawing No.:** 5 of 6


**File Path:** N:\9811V - Walker Upper Quarry Drawings\Site Plan\CAD\9811V - Site Plan.dwg




Section A-A' - Existing  
Horizontal - 1:2500  
Vertical - 1:500



Section A-A' - Rehabilitation  
Horizontal - 1:2500  
Vertical - 1:500




Section B-B' - Existing  
Horizontal - 1:2500  
Vertical - 1:500



Section B-B' - Rehabilitation  
Horizontal - 1:2500  
Vertical - 1:500

Cross Section Key Map  
Scale 1:4000



- Legal Description**  
Part of Lots 119, 120, 136 & 137  
City of Niagara Falls (Geographic Township of Stamford)  
Regional Municipality of Niagara
- Legend**
- Licence Boundary
  - Limit of Extraction
  - Additional Lands Owned by Licensee Applicant
  - Municipal Boundary
  - 120m Offset From Licence Boundary
  - Public Road
  - Trans Canada Pipeline Easement
  - Hydro One Easement
  - Cross Sections

- Legend - Cross Sections**
- Licence Boundary
  - Limit of Extraction
  - Existing Grade - Undisturbed
  - Existing Grade - Removed / Altered
  - Berm
  - Maximum Predicted Water Table (See note A.2 on drawing 5 of 6)
  - Quarry Floor / Face
  - Topsoil and/or Overburden
  - Aggregate Available for Extraction
  - Backfilled
  - Lake or Pond
  - Hydro Corridor

**Site Plan Amendments**

No.	Date	Description	By

**Site Plan Revisions (Pre-Licensing)**

No.	Date	Description	By
1	January 2022	Updated site plan per feedback from MNRF and completed minor housekeeping	C.P.
2	August 2023	Updated site plan to incorporate JART and MNRF comments	C.P.
3	April 4, 2024	Updated site plan to incorporate JART and MNRF comments	C.P.

**MHBC**  
PLANNING  
URBAN DESIGN  
& LANDSCAPE  
ARCHITECTURE  
113 COLLIER STREET, BARRE, ON, L4M 1H2 | P: 705.728.0045 F: 705.728.2010 | WWW.MHBCA.LC.M

**MHBC Stamp**  
Debra Walker  
Is authorized by the Ministry of Northern Development, Natural Resources and Forestry pursuant to Subsection 0.2(3)(f) of the Ontario Regulation 244/97 to prepare and certify site plans.

**MHBC Stamp**  
Christopher Poole  
Is authorized by the Ministry of Northern Development, Natural Resources and Forestry pursuant to Subsection 0.2(3)(f) of the Ontario Regulation 244/97 to prepare and certify site plans.

**Applicant**  
Walker Aggregates Inc.  
2800 Thord Townline Road  
P.O. Box 100  
Thord, Ontario  
L2V 3Y8

**Project**  
Upper's Quarry

**MNRF Licence Reference No.** / **Applicant's Signature**

**Plan Scale:** (Arch E) / **Date:** October 2021 April 4, 2024

**Horizontal:** 1:2500 / **Vertical:** 1:500 / **Drawn By:** C.P. / **File No.:** 9811V

**Checked By:** D.W.

**File Name:** Cross Sections

**Drawing No.:** 6 of 6

**File Path:** N:\8911V - Walker Upper Quarry\Drawings\Site Plan\CAD\811V - Site Plan.dwg


See Section F on drawing 4 of 6 for Traffic Report Recommendations

**UPPERS QUARRY - THOROLD TOWNLINE ROAD**  
UPPERS LANE CONCEPTUAL INTERSECTION DESIGN  
OPTION 1: SOUTHBOUND SLIP AROUND LANE

**TMIG**

**UPPERS QUARRY - THOROLD TOWNLINE ROAD**  
UPPERS LANE VEHICLE MOVEMENT DIAGRAM  
QUARRY TRUCK INBOUND AND OUTBOUND MANOEUVRES

**TMIG**



10138 Beaversdam Road

9417 Beaversdam Road

9722 Beaversdam Road

10148 Beaversdam Road

9602 Beaversdam Road

9582 Beaversdam Road

9337 Beaversdam Road

Beaversdam Rd

MULHERN.

Thorold Townline Rd

4832 Thorold Townline Road - Utilities

5329 Beechwood Road

5584 Beechwood Road

5769 Beechwood Road

5821 Beechwood Road

9941 Lundy's Lane

6200 Thorold Townline Road

58

70

20

Niagara Falls Golf Club

Google Earth

Kalar Rd

Kalar Rd

# Appendix B



## Uppers Quarry

### PREVAILING METEOROLOGICAL CONDITIONS

Medians provided by Environment Canada  
Canadian Climate Normals 1981-2010  
St Catherines – Municipal Airport

Date	Wind Direction	Max Hourly Wind Velocity Km/h	Temperature (Deg Celsius)
January	SW	89	-3.8
February	E	63	-2.9
March	SW	74	1.1
April	SW	74	7.4
May	SW	65	13.7
June	SW	65	19.0
July	SW	63	21.9
August	W	59	20.8
September	W	53	16.6
October	SW	63	10.4
November	SW	70	4.6
December	SW	70	-0.9

# Appendix C

Ground Vibrations

<b>Imperial Equations</b>				
Equation 1	Equation 2	Equation 3	Equation 4	Equation 5
Oriard 50% Bound (2002)	Oriard 90% Bound (2002)	Typical Production Blast (Bulletin 656 – 1971)	Typical limestone Quarry (Pader report – 1995)	Typical Coal Mine (RI8507 1980)
$v = 160 \left(\frac{D}{\sqrt{W}}\right)^{-1.6}$	$v = 242 \left(\frac{D}{\sqrt{W}}\right)^{-1.6}$	$v = 182 \left(\frac{D}{\sqrt{W}}\right)^{-1.82}$	$v = 52.2 \left(\frac{D}{\sqrt{W}}\right)^{-1.38}$	$v = 133 \left(\frac{D}{\sqrt{W}}\right)^{-1.5}$

<b>Metric Equations</b>			
Equation 1	Equation 2	Equation 3	Equation 4
DuPont General (1968)	Construction Blasting (Dowding 1998)	Agg. Quarry Blasting (Explotech 2005)	Agg. Quarry blasting (Explotech 2003)
$v = 1140 \left(\frac{D}{\sqrt{W}}\right)^{-1.6}$	$v = 1326 \left(\frac{D}{\sqrt{W}}\right)^{-1.38}$	$v = 5175 \left(\frac{D}{\sqrt{W}}\right)^{-1.76}$	$v = 7025 \left(\frac{D}{\sqrt{W}}\right)^{-1.85}$

D (m)	W (Kg)	PPV1 (mm/s)	PPV2 (mm/s)	PPV3 (mm/s)	PPV4 (mm/s)	PPV5 (mm/s)	PPV1 (mm/s)	PPV2 (mm/s)	PPV3 (mm/s)	PPV4 (mm/s)
710	118	1.4	2.2	0.5	1.4	1.9	1.4	4.1	3.3	3.1

Air Overpressure

<b>Imperial Equations</b>			
Equation 1	Equation 2	Equation 3	Equation 4
USBM RI8485 (Behind Blast)	USBM RI8485 (Front of Blast)	USBM RI8485 (Full Confined)	Construction Average
$P = 0.056 \left(\frac{D}{\sqrt[3]{W}}\right)^{-0.515}$	$P = 1.317 \left(\frac{D}{\sqrt[3]{W}}\right)^{-0.966}$	$P = 0.061 \left(\frac{D}{\sqrt[3]{W}}\right)^{-0.96}$	$P = 1 \left(\frac{D}{\sqrt[3]{W}}\right)^{-1.1}$

<b>Metric Equations</b>		
Equation 1	Equation 2	Equation 3
Ontario Quarry (Explotech 2013)	Limestone (Explotech 2011)	Ontario Quarry (Explotech 2012)
$P = 159 \left(\frac{D}{\sqrt[3]{W}}\right)^{-0.0456}$	$P = 206 \left(\frac{D}{\sqrt[3]{W}}\right)^{-0.1}$	$P = 1222 \left(\frac{D}{\sqrt[3]{W}}\right)^{-0.669}$

D (m)	W (Kg)	OP1 (dB)	OP2 (dB)	OP3 (dB)	OP4 (dB)	OP1 (dB)	OP2 (dB)	OP3 (dB)
710	118	119.3	123.6	97.3	114.4	126.7	125.3	126.8

# Appendix D

# EXPLOTECH

Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

**Robert J. Cyr, P. Eng.**  
Principal, Explotech Engineering Ltd.

## EDUCATION

Bachelor of Applied Science,  
Civil Engineering, Queen's University

## PROFESSIONAL AFFILIATIONS

Association of Professional Engineers of Ontario (APEO)  
Association of Professional Engineers and Geoscientists of BC (APEG)  
Association of Professional Engineers, Geologists and Geophysicists of Alberta  
Association of Professional Engineers and Geoscientists of New Brunswick  
Association of Professional Engineers of Nova Scotia  
Association of Professional Engineers and Geoscientists Manitoba  
Professional Engineers and Geoscientists Newfoundland and Labrador  
Northwest Territories and Nunavut Association of Professional Engineers (NAPEG)  
International Society of Explosives Engineers (ISEE)  
Ontario Stone Sand & Gravel Association (OSSGA)  
Surface Blaster Ontario Licence 450109

## SUMMARY OF EXPERIENCE

Over thirty five years experience in many facets of the construction and mining industry has provided the expertise and experience required to efficiently and accurately address a comprehensive range of engineering and construction conditions. Sound technical training is reinforced by formidable practical experience providing the tools necessary for accurate, comprehensive analysis and application of feasible solutions. Recent focus on vibration analysis, blast monitoring, blast design, damage complaint investigation for explosives consumers and specialized consulting to various consulting engineering firms.

## PROFESSIONAL RECORD

2001 – Present	-Principal, Explotech Engineering Ltd.
1996 – 2001	-Leo Alarie & Sons Limited - Project Engineer/Manager
1993 – 1996	-Rideau Oxford Developments Inc. – Project Manager
1982 – 1993:	-Alphe Cyr Ltd. – Project Coordinator/Manager

---

**EXPLOTECH ENGINEERING LTD.**

**Ottawa ♦ Sudbury ♦ Toronto ♦ Halifax**

**WWW.EXPLOTECH.COM**

**1-866-EXPLOTECH**



Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

**Mitch Malcomson, P.Eng.**  
Consulting Engineer, Explotech Engineering Ltd.

## **EDUCATION**

Bachelor of Engineering,  
Civil Engineering with Concentration in Business Management,  
Carleton University

## **PROFESSIONAL AFFILIATIONS**

Association of Professional Engineers of Ontario (APEO)  
Association of Professional Engineers and Geoscientists of BC (APEG)  
International Society of Explosives Engineers (ISEE)  
Ontario Stone Sand and Gravel Association (OSSGA)

## **SUMMARY OF EXPERIENCE**

A Consulting Engineer and Project Manager for Explotech Engineering Ltd., Mitch holds a Bachelor of Engineering degree from Carleton University in Civil Engineering with a Concentration in Business Management. Mitch has strong analytical, technical, business and leadership skills. As a Project Manager, Mitch is responsible for operational strategies, scheduling and contract procurement. As a Consulting Engineer, the technical responsibilities include detailed blast designs, blast investigations and reviews, implementation of vibration monitoring programs, development of monitoring equipment/ technologies and building assessments for construction and the drilling and blasting portions of mining, quarrying and construction projects across Canada.

## **PROFESSIONAL RECORD**

2008 – Present - Consulting Engineer / Project Manager, Explotech Engineering Ltd.



Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

Andrew Campbell, P.Eng.  
Explotech Engineering Ltd.

## EDUCATION & QUALIFICATIONS

Bachelor of Engineering,  
Mechanical Engineering, Carleton University

Advanced and Expert (Industry) CadnaA Modelling  
DataKustik, Mississauga, Ontario

## PROFESSIONAL AFFILIATIONS

Association of Professional Engineers of Ontario (APEO)  
International Society of Explosive Engineers (ISEE)

## SUMMARY OF EXPERIENCE

An engineer working for Explotech Engineering Ltd., Andrew holds a Bachelor of Engineering degree in Mechanical Engineering and has strong analytical, technical, and interpersonal skills. A proven leader in collaborative environments, Andrew is comfortable managing projects, specifying details, and communicating internally and externally. With a focus on blast designs, blast impact analyses, noise monitoring and modelling, damage complaint investigations, vibration analysis, and blast monitoring, Andrew has applied these skills across Canada.

## PROFESSIONAL RECORD

- 2018 – Present - Engineer, Explotech Engineering Ltd.
- 2013 – 2018 - Technician / EIT, Explotech Engineering Ltd.
- 2012 – 2012 - Ride Technician, Canada's Wonderland



Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

Michael Tobin, P.Eng.

Explotech Engineering Ltd.

## EDUCATION

Bachelor of Applied Science,  
Geological Engineering, Queen's University

## PROFESSIONAL AFFILIATIONS

Association of Professional Engineers of Ontario (APEO)  
International Society of Explosives Engineers (ISEE)

## SUMMARY OF EXPERIENCE

An engineer working for Explotech Engineering Ltd., Michael holds a Bachelor of Applied Science degree from Queen's University in Geological Engineering. Michael has strong analytical, technical, and interpersonal skills. Recent projects have focused on blast monitoring, vibration analysis, job estimation, damage complaint investigation and blast design.

## PROFESSIONAL RECORD

- 2021 – Present - Engineer, Explotech Engineering Ltd.
- 2017 – 2021 - Technician, Explotech Engineering Ltd.

# Appendix E



## Blasting Terminology

ANFO:	Ammonium Nitrate and Fuel Oil – explosive product
ANFO WR:	Water resistant ANFO
Blast Pattern:	Array of blast holes
Body hole:	Those blast holes behind the first row of holes (Face Holes)
Burden:	Distance between the blast hole and a free face
Column:	That portion of the blast hole above the required grade
Column Load:	The portion of the explosive loaded above grade
Collar:	That portion of the blast hole above the explosive column, filled with inert material, preferably clean crushed stone
Face Hole:	The blast holes nearest the free face
Overpressure:	A compressional wave in air caused by the direct action of the unconfined explosive or the direct action of confining material subjected to explosive loading.
Peak Particle Velocity:	The rate of change of amplitude, usually measured in mm/s or in/s. This is the velocity or excitation of the particles in the ground resulting from vibratory motion.
Scaled distance:	An equation relating separation distance between a blast and receptor to the energy (usually expressed as explosive weight) released at any given instant in time.
Sensitive Receptor:	Sensitive land use may include recreational uses which are deemed by the municipality or provincial agency to be sensitive; and/or any building or associated amenity area (i.e. may be indoor or outdoor space) which is not directly associated with the industrial use, where humans or the natural environment may be adversely affected by emissions generated by the operation of a nearby industrial facility. For example, the building or amenity area may be associated with residences, senior citizen homes, schools,

# EXPLOTECH

day care facilities, hospitals, churches and other similar institutional uses, or campgrounds.

Spacing:	Distance between blast holes
Stemming:	Inert material, preferably clean crushed stone applied into the blast hole from the surface of the rock to the surface of the explosive in the blast hole.
Sub-grade:	That portion of the blast hole drilled and loaded below the required grade
Toe Load:	The portion of explosive loaded below grade



## References

Building Research Establishment, (1990), *"Damage to Structures From Ground-Borne Vibration"*, BRE Digest 353, Gaston, Watford, U.K.

Crum S. V., Siskind D. E., Pierce W. E., Radcliffe K. S., (1995) *"Ground Vibrations and Airblasts Monitored in Swedesburg, Pennsylvania, From Blasting at McCoy Quarry"*, Contract Research Rept. By the United States Bureau of Mines for the Pennsylvania Department of Environmental Resources, 120 pp.

Dowding C.H., (1985), *"Blast Vibration, Monitoring and Control"*, Prentice-Hall Canada Inc., 297 pp.

Dowding C.H., (1996), *"Construction Vibrations"*, Prentice-Hall, Upper Saddle, N.J., USA, 610 pp.

Du Pont Company, (1980), *"Blaster's Handbook"* Wilmington, Delaware, United States of America

Fletcher L.R., D'Andrea D.V., (1986) *"Control of Flyrock in Blasting"*, Proceedings of the Twelfth Annual Conference on Explosives and Blasting Technique, International Society of Explosives Engineers

Froedge D. T., (1983) *"Blasting Effects on Water Wells"*, Proceedings of the Ninth Annual Conference on Explosives and Blasting Technique, International Society of Explosives Engineers

Kopp J.W., (1994) *"Observation of Flyrock at Several Mines and Quarries"*, Proceedings of the Twentieth Annual Conference on Explosives and Blasting Technique, International Society of Explosives Engineers

Matheson G. M., Miller D. K., (1997) *"Blasting Vibration Damage to Water Supply, Well Water Quality and Quantity"*, Proceedings of the Twenty-Third Conference on Explosives and Blasting Technique, International Society of Explosive Engineers

Moore A.J., Richards A.B., (2005), *"Golden Pike Cut-Back Flyrock Control and Calibration of a Predictive Model"*, Terrock Consulting Engineers, Eltham, Victoria, Australia.

# EXPLOTECH

Nicholls H., Johnson C., Duvall W., (1970), "*Blasting Vibrations and their Effects on Structures*", United States Department of the Interior, Bureau of Mines, Bulletin 656

Oriard L.L., (1989) "*The Scale of Effects in Evaluating Vibration Damage Potential*" Fifteenth Conference on Explosives and Blasting Technique, International Society of Explosive Engineers

Oriard L.L., (2002) "*Explosives Engineering, Construction Vibrations and Geology*" International Society of Explosive Engineers, Cleveland, Ohio, United States of America

Robertson D. A., Gould J. A., Straw J. A., Dayton M. A., (1980) "*Survey of Blasting Effects on Ground Water Supplies in Appalachia*", United States Department of the Interior, Bureau of Mines, Contract No. J-0285029

Rose R., Bowles B., Bender W. L., (1991) "*Results of Blasting in Close Proximity to Water Wells at the Sleeper Mine*", Proceedings of the Seventeenth Annual Conference on Explosives and Blasting Technique, International Society of Explosive Engineers

Roth J., (1979) "*A Model for Determination of Flyrock Range as a Function of Shot Conditions*", United States Department of the Interior, Bureau of Mines, Report OFR 77-81

Siskind D.E., Stagg M.S., Kopp J.W., Dowding C.H., (1980), "*Structural Response and Damage Produced by Ground Vibration from Surface Mine Blasting*", United States Bureau of Mines RI 8507.

White, T.J., Farnfield, R.A., Kelly, M., (1993), "*The Effect of Low Level Blast Vibrations and the Environment on a Domestic Building*", Proceedings of the Ninth Annual Symposium on Explosives and Blasting Research, International Society of Explosives Engineers.

Wright D.G., Hopky G. E., (1998) "*Guidelines for the Use of Explosives In or Near Canadian Fisheries Waters*", Canadian Technical Report of Fisheries and Aquatic Sciences 2107